

LEAST-COST ELECTRIC POWER SYSTEM DEVELOPMENT ANALYSIS
For
European Bank for Reconstruction and Development

UKRAINE
Completion of
Khmelnitsky 2 and Rovno 4
Nuclear Power Generators
Economic Due Diligence



May 1998

Stone & Webster Management Consultants, Inc.
Englewood, Colorado, USA

Khmelnitsky 2 & Rovno 4
Completion Due Diligence
Least Cost Plan

May 1998
for EBRD
Stone & Webster

Table of Contents

Executive Summary

| | |
|-----------------------------------|---|
| Executive Summary | 1 |
| Assumptions | 1 |
| Sensitivity Analysis | 2 |
| Probabilities of being least-cost | 3 |
| Decision Risk | 4 |
| Conclusion | 5 |

Main Report

| | | |
|------------|--|----|
| 1. | Introduction | 7 |
| | A. Purpose of the Analysis | 7 |
| | B. Previous Studies | 7 |
| 2. | Methodology | 9 |
| | A. Range of Alternatives | 9 |
| | B. Evaluation Approach | 11 |
| | C. Model Description | 13 |
| 3. | Data Development | 14 |
| | A. Sources | 14 |
| | B. Review Process | 14 |
| | C. Planning Assumptions | 14 |
| | D. Probabilities of Occurrence | 17 |
| 4. | Analytical Process | 18 |
| 5. | Results | 20 |
| | A. Screening Curves | 20 |
| | B. Base Case Scenario | 21 |
| | C. Probability Analysis | 21 |
| | D. Decision Risk | 28 |
| 6. | Conclusions | 34 |
| Appendix A | Data Tables | |
| Appendix B | Case Summaries | |
| Appendix C | Decision Trees | |
| Appendix D | Comparison of Surrey Panel Report and S & W Report | |
| Appendix E | Plant Additions for Base Case Scenario | |

UKRAINE
Completion of Khmelnytsky 2 and Rovno 4 Nuclear Power Generators
Economic Due Diligence
LEAST-COST ELECTRIC POWER SYSTEM DEVELOPMENT ANALYSIS
For
European Bank for Reconstruction and Development

Executive Summary

This analysis was undertaken on behalf of the European Bank for Reconstruction and Development as part of the economic due diligence on completion of the two Ukrainian nuclear power generating units Khmelnytsky 2 ("K2") and Rovno 4 ("R4"), which are already about 80% built.

The analysis determines whether the completion of K2 and R4 by 2002 is likely to form part of the least-cost development program for meeting demand on the Ukrainian power system over the long term ("least-cost"). Costs are expressed in economic terms, that is in constant 1997 prices excluding Ukrainian direct taxes and interest during construction. They comprise the construction costs of new power generating plant, the rehabilitation costs of existing power plant, decommissioning costs, and the operating costs of both existing and new plant (including fuel and waste disposal costs). Each cost is discounted to present (1997) values at 10% from the time that it is incurred.

The completion of K2 and R4 is evaluated as a component of an integrated program of investments over a long period, taken to be between 1998 and 2010, rather than as an isolated investment. The analysis considers investments in other forms of power supply capacity - both rehabilitation and construction - besides K2 and R4, as well as in measures that modify the demand of electricity users. The least-cost program is identified as the sequence of investments selected from these options that result in system demand being met at the lowest total cost in present value terms. The analysis was performed with the widely accepted EGEAS power planning model.

Assumptions

The analysis requires extensive data about the performance of existing power plants, which have a combined capacity of about 50,000 MW, and of options for developing the power system. A considerable effort has been made to gather reliable data, firstly from previous studies conducted in the last five years. Subsequently, a week-long review of the required data was carried out among interested parties at a meeting in Kiev, which resulted in a set of data that has been agreed to represent the Ukrainian power system reasonably well.

The approach used for the analysis specifically takes into account the significant uncertainty about future power demand, construction costs and fossil fuel costs in

Ukraine. The forecast or estimate of each of these key planning variables is thus expressed in terms of a range of values, rather than as a single value. This range is expressed in three values - low, middle and high - and each of these values is assigned the following relative probability of occurrence:

- for forecasts of power demand - 50% for the middle forecast of 28% increase between 1997 and 2010, and 25% each for the low forecast and high forecast;
- for fossil fuel prices - 50% for the middle forecast (gas at US\$2.65/GJ, heavy fuel oil US\$2.82/GJ, raw coal US\$1.50/GJ, all delivered to power plant), and 25% each for the low forecast and high forecast;
- for costs of completing K2 and R4 as a single project - 40% for the middle estimate of US\$ 1,181 million, 34% for the low estimate of US\$ 984 million, and 26% for the high estimate of US\$ 1,582 million.

For a given planning scenario, one of each set of the three values is selected for the key planning variables - power demand, completion cost for K2 and R4, and fossil fuel prices, producing a total of 27 scenarios for analysis.

The analysis assumed that Chernobyl Nuclear Power Station will be permanently closed by the year 2000 in accordance with the Memorandum of Understanding between Government of Ukraine and the G-7 of 20 December 1995.

Sensitivity analysis

In the base case planning scenario, in which the planning variables take their middle values, completion of both K2 and R4 in 2002 is part of the least-cost program.

The following sensitivity cases were carried out to show whether the completion of K2 and R4 in 2002 remains least-cost under a substantial change in the value of each of the key planning variables from its middle value. These tests assume that the other variables keep their middle values. The magnitude of the key variable changes and the corresponding results are summarized below:

- *The break-even economic cost of completing both K2 and R4* above which the least-cost timing for completion is later than 2002; this cost is approximately \$1490 million, which is 26% higher than the "expected" middle value for joint completion cost.
- *a major contraction of Ukrainian electricity consumption.* (i) The system load is assumed to stay at the lowest level of the low load forecast, 154,800 GWh, instead of rising to 223,500 GWh by 2010; in this case K2 is selected in 2002 as part of the least-cost program, while R4 is not selected. (ii) The system load is assumed to drop by 17% from the 1997 level to 145,000 GWh in 2000, and from that point the load is assumed to grow at the same rate (4% per year) as in the low load forecast; in this case, the least-cost program includes completion of K2 in 2002 and R4 in 2005.
- *The cost of gas falls from the present level* of \$2.65/GJ to a level that displaces the least-cost timing for completing K2 and R4 from 2002. Under a 28% fall in gas cost to \$1.92/GJ, K2 is least-cost in 2002 and R4 is least-cost in 2004. Under a 32% fall in

gas cost to \$1.80/GJ, K2 is least-cost in 2003 and R4 is least-cost in 2005.


- *The opportunity cost of capital to Ukraine (the discount rate) is higher than 10%. At 13%, K2 is least-cost in 2003 and R4 is least-cost in 2005. At 16%, K2 is least-cost in 2006 and R4 is least-cost in 2009. At 20%, K2 is least-cost in 2007 and R4 is least-cost in 2009.*

Probabilities of being least-cost

Because of the uncertainty about future values for the planning parameters, however, the base case scenario has only a relatively small probability of occurrence, equal to 10% ($0.5 \times 0.4 \times 0.5 = 0.10$). The objective of the analysis is thus to determine the probability that the completion of K2 and R4 in 2002 is part of the least-cost power development program over all the planning scenarios. This probability is defined as the sum of the relative probabilities of the scenarios in which completion of K2 and R4 in 2002 is part of the least-cost power development program.

The analysis shows that a decision to complete both K2 and R4 in 2002 has 50% probability of being least-cost. Completing K2 in 2002 and R4 in 2003 as a joint completion project has a 64% probability of being least-cost. The lower probability for R4 is accounted by the additional cost of transmission facilities needed for R4 which are not incurred for K2. A greater spread than two years in time loses the cost advantages of joint completion, and would be considered sequential completion (see below).

The probabilities that completion of K2 and R4 jointly are least-cost increase markedly towards 100% at later completion dates, as shown in the following graph.



A decision to complete K2 in 2002 and R4 one or two years later would have a higher overall probability of being least cost than the probability of completing both units in 2002. This is because the probability is relatively high that completing K2 in 2002 is least cost, and the probability that completing R4 later than 2002 is least cost increases substantially above 50%.

Evaluation was conducted of sequencing completion first of K2 and then R4 as separate projects. Under this approach, K2 was considered to be completed in 2002 and then R4 completed as a separate project in its own least-cost timing, but no sooner than 2005. A decision to sequence the completion of the units involves a total completion cost that is about 9% higher than the total cost of completing the units together. This results from the loss of the savings from incurring only one set of mobilization costs and sharing staff, parts ordering, etc., that is achieved when the units are completed together. The rationale for deliberately delaying completion of R4 is to gain additional insight on potential adverse outcomes of the key planning variables before committing the capital to complete R4. Nevertheless, the analysis shows that sequential completion of the units makes little difference to the probabilities of least-cost timing for R4 completion shown above.

K2 and R4 are the only new additions to system supply capacity that are likely to be least-cost. They are needed to substitute high cost energy produced from existing unrehabilitated fossil fuel plant, even though the present (1997) installed capacity in the power system is technically sufficient (but not economically the best) to supply system energy needs and peak load until around 2007. The other least-cost investments in supply capacity up to 2010 cover rehabilitation and upgrading of existing nuclear and fossil fuel plant. The least-cost development program is thus basically a rehabilitation program, not an expansion one. Notably, it results in a major improvement in energy efficiency and reduction in harmful emissions from power plants over present levels for the Ukrainian power system.

Decision risk

Given that a decision to complete both K2 and R4 in 2002 is not certain to be least-cost, the economic risk of proceeding with this decision should be compared with the economic risk of making other decisions about completing K2 and R4 instead. The economic risks for two other decisions were thus analyzed, namely first to complete K2 in 2002 and R4 no earlier than 2005 and later if least-cost, as indicated above; and second not to complete K2 and R4 before 2010.

For the purposes of the analysis, the economic risk of a decision about when to complete K2 and R4 is the difference between the total cost of the least-cost development program with the completion date of K2 and R4 constrained according to the decision, and the total cost of the least-cost development program without any constraint. The amount of this cost difference varies with planning scenario.

The risk of incurring excess cost from a decision about when to complete K2 and R4 arises from the uncertainty about which planning scenario will actually materialize. The least-cost timing for completing K2 and R4 under the scenario that actually happens may differ from the least-cost timing for the assumptions upon which the decision is based. The decision risk for completing the units in 2002 is that the scenario that actually occurs carries least-cost completion of one or both units in later years. The decision risk for deferring completion of R4 until 2005 or later is that the scenario that actually occurs carries least-cost completion for R4 before 2005. The decision risk for not completing the units by 2010 is that the scenario that actually occurs carries least-cost completion of one or both units before 2010.

The excess cost from this risk was assessed for each of the 27 scenarios. The analysis shows that under most scenarios (15 out of 27), there is no or negligible cost risk in deciding to complete K2 and R4 in 2002. The highest present value cost risk of this decision is \$149 million, a scenario that includes the high value for K2/R4 completion cost, the low load forecast and the low fossil fuel cost. The average cost risk of completing both K2 and R4 in 2002 is \$22 million.

In none of the scenarios is the exclusion of K2 and R4 least cost. The cost penalty of not completing K2 and R4 ranges from a present value of \$20 million to one of \$657 million. The average cost risk of not completing K2 and R4 is \$322 million, which shows that there is a major cost risk in deciding not to complete them by 2010.

The present value cost of sequencing the completion of R4 after completing K2 in 2002 averages \$114 million more than the cost of completing them at the least-cost timing. The present value cost of sequencing the completion of the two units averages \$92 million more than the average cost of completing them together in 2002. This is because 26 of the 27 scenarios show lower cost for joint completion in 2002 over sequential completion. Hence, the decision to complete both K2 and R4 in 2002 carries the lowest cost risk of these three decisions.

Conclusion

The analysis of whether completion of K2 and R4 in 2002 is likely to be least-cost leads to the following conclusions:

- 2002 is the least-cost timing for K2 and R4 in the base case scenario;
- the completion timing of 2002 for K2 and R4 in the base case is robust in the sensitivity tests;
- completion of K2 and R4 jointly in 2002 has a 50% probability of being least cost under scenario analysis;
- completion of K2 in 2002 and R4 in 2005 or later as a sequential project is likely to be higher cost than completion of both units jointly in 2002;
- the decision to complete K2 and R4 jointly in 2002 is the least risky choice in terms of economic cost.

On the basis of these combined conclusions from the sensitivity analysis, the probability analysis and the decision risk analysis, the decision to complete both Khmel'nitsky 2 and Rovno 4 in 2002 is likely to be the least-cost and least risky economic choice.

MAIN REPORT

1. Introduction

A. Purpose of the Analysis

This analysis was undertaken on behalf of the European Bank for Reconstruction and Development (EBRD) as part of the economic due diligence for completing and operating two nuclear power generating units, designated Khmelnytsky 2 ("K2") and Rovno 4 ("R4"). These units are partially completed, with approximately 80% of construction in place. Both units are located at sites already having at least one operating nuclear unit. These two partially complete units are of the Russian VVER-1000 design. Besides the Chernobyl Nuclear Power Station, the nuclear power utility, Energoatom, now operates a total of 13 nuclear generating units, eleven of which are of the VVER-1000 type and two are of the VVER-440 type.

B. Previous Studies

This study is the latest in a series of studies addressing the issue, either directly or tangentially, of whether completion of K2 and R4 are part of the least-cost power development program for Ukraine.

The studies known to be available are:

- "Ukraine – Power Sector Least Cost Investment Plan," Main Report, Lahmeyer International, July 1995
- "Economic Assessment of the Khmelnytsky 2 and Rovno 4 Nuclear Reactors in Ukraine, Science Policy Research Unit, University of Sussex, 4 February 1997 (Surrey Panel Report)
- Previous Stone & Webster Report of May, 1997

Also, the following reports have contributed information to the pool of data that could be drawn upon for this analysis:

- "Staff Appraisal Report, Ukraine, Electricity Market Development Project," World Bank, Sept. 16, 1996, Report No. 15450-UA
- "Energy Policies of Ukraine, 1996 Survey" International Energy Agency
- "Ukraine Thermal Power Plant Rehabilitation Study," Draft Main Report, Kema Consultants, August 10, 1994 and addenda, for World Bank
- "Cost Estimates and Financial Evaluations, Ukraine Thermal Power Plant Rehabilitation Study," draft report, Comprimo Consultants as sub-contractor to KEMA, 2 August, 1994, for World Bank
- "Ukraine Fossil Fuel Power Plant Efficiency Study, Main Report, ESB International, January 1994, for EBRD
- "Joint Parallel Nuclear Alternatives Study for Russia," Final Report, U.S. Dept. of Energy and Ministry of Atomic Energy of the Russian Federation,

June 1995

- “Demand-Side Management in Ukraine, Part 1: National Assessment,”
Final Draft Report, Hagler Bailly Consulting, Inc., September 15, 1995

In brief, the Lahmeyer study and the previous Stone & Webster Study concluded that the Khmel'nitsky 2 and Rovno 4 nuclear power plants should be completed immediately as part of the least-cost development plan for the Ukrainian electricity sector. The Surrey Panel Report recommended that they not be completed. A comparison of the Surrey Panel Report's recommendations and those of this report, together with an explanation of the differences, is included in Appendix D of this report.

2. Methodology

A. Range of Alternatives

The approach to the evaluation of completing K2 and R4 considered both supply-side and demand-side options to find the long-term development program for the whole power system that meets forecast electricity demand at least total economic cost.

A considerable degree of uncertainty exists about the values that will exist for a number of key variables in this analysis. An important element in the analysis has thus been to identify these key variables and to establish a range of their possible outcomes. Previous studies have offered valuable insights on these choices. The key variables are:

- Energy demand and peak load forecast
- K2 and R4 completion cost (including decommissioning and transmission)
- Fossil-fuel unit rehabilitation costs
- Fuel costs

Considerable research, as noted above, has been performed on possible equipment alternatives that could be used to improve the performance of the Ukrainian electricity generating stations. Proposals have included:

- A broad range of fossil-fueled power plant rehabilitation
- Nuclear unit completion for partially-constructed units
- Performance upgrade of existing nuclear units
- New stand-alone fossil-fueled power plants
- Combined heat and power production facilities
- Completion of a partially-constructed pumped storage power plant
- Solar, wind and biomass-fueled power plants

Also, energy conservation measures have been proposed and studied for their applicability, as noted above in the list of studies previously undertaken. The use of energy conservation measures is considered especially important since the large base of industrial use has been shown to be much less energy-efficient than similar industries in the West. This has been largely attributed to the lack of requirement for users to pay for the amount of electricity used at cost of service rates.

The only assumption that was treated as certain for the analysis was the permanent closure of Chernobyl Nuclear Power Station in 2000 in accordance with the Memorandum of Understanding between Government of Ukraine and the G-7 of 20 December 1995.

In addition, the existing production capacity of the Ukrainian power system was considered, for which an amount of 50,000 MW was included in the analysis. This total

comprised 24% nuclear power (excluding Chernobyl NPP), 56% fossil fuel plant, 9% hydropower capacity, and 11% combined heat and power plant. Some of the fossil fuel plant was assumed to be retired during the planning period up to 2010 according to a schedule provided by the Ministry of Energy and Electrification in Kiev.

The existing fossil fuel generating plants need extensive repair and rehabilitation. Large quantities of natural gas are being used as a co-firing fuel in most units to maintain combustion and to provide adequate boiler heat input for full load operation. Various levels of co-firing, ranging up to 50%, are being used. Reports of low availability of almost all the fossil-fueled units, deteriorating condition of most of the boiler and flue gas pass equipment at these plants, and poor quality coal causing pulverizer, electrostatic precipitator, and other problems indicated that a major redevelopment effort will eventually be required. Alternatives that reflected the need for repair or replacement were thus considered. Also, the opportunity to take advantage of already-completed construction, which will have to be paid for anyway, was considered. This included the two nuclear units and the Dniester Pumped Storage Station.

Energy conservation and demand-side management programs that would be competitive with supply-side costs were explored and included. The Hagler Bailly Study has sufficient documentation of the DSM programs for modeling purposes, so all of the programs included in that study were considered, a total potential of approximately 500 MW.

Three different new plant types were included in the list of alternatives. These were: coal-fired atmospheric fluidized bed combustion (AFBC) boiler steam plant, gas-fired combined cycle, and gas-fired open cycle combustion turbines. These options represent a range of fuel costs, capital costs and efficiencies considered reasonable for Ukrainian conditions. The new AFBC plant was assumed to burn the residue from washed coal, known as schlamm, mixed with a small percentage of unwashed Ukrainian coal (based on the ongoing modernization of Unit 4 at Starobeshevo Power Station). The rehabilitation option with an AFBC replacement boiler combines with the existing turbine and generator to extend the working life of the production unit. Besides taking advantage of the low economic cost of schlamm and the sunk costs in turbines and generators, the AFBC option also virtually eliminates sulfur emissions and the use of gas and heavy fuel oil to support combustion of low quality coal, and it greatly reduces ash emissions.

Renewables such as solar and wind energy plants were not considered as options for new capacity in this study since no background work was found to support solarization, wind potential or costs for these types of generation in Ukraine. In general, it is unlikely that their present high unit capital costs could be recovered at viable rates under the expected low level of system marginal prices in the Ukrainian wholesale electricity market. Also, a brief look at climatological conditions produced a discouraging outlook for them (except for a modest amount of windpower in Crimea).

Use of existing combined heat and power (CHP) plants was included. These included the plants in the Kiev and Kharkov areas as well as 3000 MW of CHP plants in other areas.

No direct consideration of new CHP plants was given in the general mix of alternatives. However, some separate cases were analyzed that modeled CHP plants burning gas in order to test their viability as differentiated from other plant types. It was found that the CHP plant costs, even with favorable cost splits with the heating loads, were no more competitive than other plant types already represented. Also, the electric system peak demand period coincides with the district heating high demand, thus reducing available electricity output when it is most needed. Since this was not a study focused on the CHP issue, it was considered adequate to have new such plants represented by a surrogate that was at least as cost effective.

In the course of the data gathering for this study, there was discussion of the relative impacts of the various alternatives on the Ukrainian environment. This was not part of the terms of reference for this study (other consultants are carrying out an Environmental Impact Assessment for K2 and R4). However, since the planning model used is capable of representing the various air pollutant emissions, data for sulfur dioxide, nitrous oxides and ash emissions were entered, and the model emission rates tested against emissions published for historical periods. No attempt to monetize the emissions was made, nor was the unit dispatch modified based on emissions rates. The model was asked just to report emission amounts in tons for the scenarios analyzed.

B. Evaluation Approach

The total economic cost of a power development program comprises construction costs of future investments in power supply facilities and the operating costs of both existing and new facilities. For this analysis costs are expressed in constant price terms (1997 US\$) without price inflation. They exclude Ukrainian direct taxes and interest during construction. Each cost is discounted to a present value (in 1997) at a rate that reflects the opportunity cost of capital to Ukraine. A 10% rate (in real terms net of inflation) was used for this analysis. The total economic cost for a development program is the sum of the discounted costs. Thus, there is a specific economic cost for each power development program. The program with the lowest economic cost is considered to be the least-cost program. Completion of K2 and R4 by a certain date, notably 2002, is considered to be economically justified if it is included in the least-cost program.

Different power development programs are evaluated under a particular set of values for the numerous planning variables involved in the analysis. In view of the considerable uncertainty about estimating future economic conditions in Ukraine, however, there is a low probability that a single planning scenario would in fact occur. Hence, the robustness of the least-cost status of completing K2 and R4 by 2002 is tested over a range of values for key planning variables - demand for power, construction costs for new capacity additions including K2/R4 and fossil-fueled plant, prices of fuels (coal, gas, heavy fuel oil), and costs of rehabilitating existing fossil fuel plant. This range is represented by three values, low, middle, and high for each variable. Each combination of values for the variables comprises a planning scenario. The combination of middle values defines a base case planning scenario that is used as a reference case. The economic justification for

completing K2 and R4 is confirmed if the least-cost development programs for most planning scenarios includes the completion of K2 and R4 in 2002.

A period of 14 years, covering the years 1997 to 2010, was used for planning investments in system capacity. In order to account for costs and benefits that might accrue after this period from investments undertaken during the planning period, an extension period of 30 years to 2040 was used for discounting to present values such benefits and costs.

Two results were sought from the analysis:

1. **Probabilities** - An estimate of the probability that completion of K2 and/or R4 by a certain year would be part of the least-cost plan. This probability was derived for a planning scenario that was defined by a combination of the various key drivers. Each of the four key drivers has three possible values. This produces a potential of 81 different scenarios for each K2/R4 completion approach, either joint completion, or sequential completion.
2. **Decision Cost Risk** - An assessment of exposure to excess cost over the least-cost option of decisions about completing K2 and R4 under the range of planning scenarios. This assessment is made for each scenario by comparing the present value of meeting forecast demand with a development program that includes the completion of K2 and R4 on specific dates, with the present value of the least-cost development program for the scenario. Zero cost risk indicates that the decision to complete K2 and R4 on the specified date(s) would be part of the least-cost development program for the planning scenario.

Three decisions were analyzed in this way regarding the completion of K2 and R4. They are:

1. **Joint Completion** - K2 and R4 are completed as a joint project, even if the dates of their completion are separated by a year or more. In this approach only one set of mobilization costs are incurred, and some sharing of common staff, parts ordering, etc., is achieved. The decision risk in this case occurs if scenarios for the future emerge in which completion of both units in 2002 is not least-cost.
2. **Sequential Completion** - K2 is completed in 2002, and R4 is completed no sooner than 2005 as a separate effort. R4 is completed after K2 because of the additional US\$67 million (in 1997 prices) cost for constructing transmission facilities to integrate Unit 4 at Rovno Nuclear Power Station into the national power transmission system, whereas no investment for transmission interconnection is needed for K2. The decision risk in this case occurs if future scenarios emerge in which completing R4 before 2005 is least-cost or completing K2 after 2002 is least-cost.

3. **No Completion** – Neither K2 and R4 are not completed by the end of the planning period, namely 2010. The decision risk in this case occurs if future scenarios emerge in which completion of one or both units before 2010 is least-cost.

Each approach has a different completion cost for each unit. That is, joint completion of the units has three possible completion costs, High, Middle and Low. Likewise, sequential completion of the units has three other possible completion costs - High, Middle and Low. The combined cost of completing K2 and R4 sequentially exceeds that of completing them jointly by 9% of the joint completion cost, amounting to US\$92 million in the Low case for completion cost, US\$110 million in the Middle case, and US\$141 million in the High case.

C. Model Description

The computer model used to conduct this study was the Electric Power Research Institute's EGEAS model. The model was originally developed in 1982 for the Electric Power Research Institute (EPRI) by Stone & Webster and the Massachusetts Institute of Technology. EGEAS is a long-term cost-optimizing model based on use of load duration curves. It includes both production costs and capital costs in its optimization process. It uses either dynamic programming or Benders Decomposition optimization techniques at the user's choice. In this study optimization was performed using dynamic programming. Since its original development Stone & Webster has maintained and upgraded the model to include modeling of demand-side management, emissions compliance planning, and competitive market analysis. It will model limited fuel use, typical weeks per month with three sub-weeks per week, variation of cost and performance parameters between and within years, and a full range of escalation rates and parameter multipliers. Both bid-based pools and traditional dispatch are available by switch setting in the model's controls.

3. Data Development

A. Sources

The preparation of the data for use in this analysis was a three-step process. Step one was to extract as much as possible of the needed data from published reports. This was accomplished with guidance from a number of knowledgeable parties interested in the analysis. A number of sources had been identified in the course of previous analyses, including those from the World Bank, Lahmeyer, KEMA, and IEA. Meetings with representatives of the World Bank and the U.S. State Department for data gathering had been held as part of the study resulting in Stone & Webster's May 1997 report.

From the sources established during prior studies, tables of needed data were developed. Lists of missing or doubtful information were then developed. There was an extensive list of items that were potentially useful, but not verified. Insofar as possible, corroboration of data for all items was sought from two or more sources. Where second sources were not possible, a check that data values were at least reasonable, given the Ukrainian system's circumstances, were made. The elements with the most difficulty were fossil unit heat rates, fossil unit availability, unit retirement/failure facts, and coal/gas co-firing rates. Many other items had less severe degrees of uncertainty about their validity.

The second step in the data gathering process was to conduct interviews. The interviews were held at the Ministry of Energy and Electrification and Energoatom in Kiev in November 1997.

Following the interviews, a meeting was held in November at the EBRD offices in London to present the data gathered to date. This series of meetings over two days resulted in a recommendation that a comprehensive data review meeting be held in Kiev as soon as it could be organized. In the course of the two days of meetings some other data sources were offered, and some information provided.

The third step in the data gathering process was to participate in the data review meeting held at the Project Management Group's offices in Kiev in early December. In anticipation of that meeting, tables of all relevant data to be used in the analysis were prepared. These data tables were sent by EBRD to parties with particular expertise in the Ukrainian power sector and power system planning in general.

B. Review Process

The data review process was held from Tuesday, December 2 to Friday, December 5, 1997 at the offices in Kiev of Energoatom's Project Management Group. The daily meetings were attended by an average of approximately thirty people from a broad cross-section of groups. These included three people from Stone & Webster, one of whom is an expert in fossil power rehabilitation, and another who is an expert in nuclear power plant

construction and licensing. Representatives of the Ukrainian Ministry of Energy and Electrification, Energoatom and the Academy of Sciences were present, some throughout the entire proceeding. Governmental groups were represented by staff members of the European Community, the U. S. Agency for International Development, and the U. S. Embassy's Office of the Commercial Attache. Engineers and other consultants working with the Project Management Group in the development of the K2 and R4 completion cost estimates were represented throughout the week. In addition to the representatives of the Ministry and the Academy, outside consultants on fuel pricing and coal industry restructuring also attended.

The process consisted of a presentation of all data items one at a time for review by the group present. Comments and suggestions were presented and discussed. The intent was to seek consensus agreement on all data items. With only a few limited exceptions, such consensus was reached. In those cases where agreement was not reached, none of which was critical to the outcome of the analysis, as it turns out, values were set by the EBRD staff after listening to the arguments favoring particular choices.

As a result of the scrutiny given in the review process, the planning data have been firmed up where more speculative values were previously available, and full advantage is taken of the engineering options available for developing the power system.

C. Planning Assumptions

Two of the World Bank's forecasts for power demand in Ukraine that were prepared in mid-1997 were used for the analysis. The World Bank's "low" forecast was used as the "middle" forecast, and the World Bank's "middle" forecast was used as the "low" forecast for the analysis. The EBRD's "middle" forecast was used as the "low" forecast for the analysis. The main difference between the latter two forecasts is that the EBRD forecast is more pessimistic about the short-term outlook up to 2000 for a turnaround in the decline in demand that has occurred since 1990.

An important consideration for specifying the planning data is the range of potential completion costs for K2 and R4. Three possible completion cost points were prepared, designated "Low", "Middle", and "High". The "Low" estimate was taken as the estimate for K2 and R4 completion prepared by Project Management Group and reviewed at the Kiev meeting. These values included estimated costs (in present value terms) of decommissioning the two plants at the end of their service lives, and in R4's case the cost of additional transmission to reliably connect the plant to the Ukrainian transmission grid. The initial cost of loading fuel into the new reactors was included in the variable operating cost during the first three years of operation, and hence were not included in the economic completion cost to avoid double counting.

The "Middle" completion cost estimate was set at an increment of 20% on top of the "Low" estimate. This is based on the experience of the World Bank that the original engineering estimates of construction costs for power generation projects have been

systematically below the actual construction costs by an average of about 20%.¹ The "Middle" completion cost estimate is thus an "expected" cost.

The "High" completion cost estimate is based on the 90% statistical probability that the actual completion cost will not exceed this amount. The factor of 1.28 by which the High cost estimate exceeds the Middle cost estimate is based on a normalized distribution of the ratio of actual cost to estimated cost for the group of World Bank-supported power generation projects referred to above.

The same principle was applied to determining the range of costs to be used for fossil-fueled plant rehabilitation projects. However, in the fossil unit rehabilitation costs, the "High" estimates were considered to exceed the "Middle" estimates by 20%, and the "Middle" estimate exceeds the "Low" estimate also by 20%.

Forecasts of fossil fuel prices were based on consensus trends. The cost of imported gas is not expected to change significantly in real terms over the foreseeable future, and so was held constant in the middle forecast at the current import price. The economic cost of domestically mined raw coal was taken to be about 20% below current coal tariffs in order to remove the estimated element of resource transfer from coal users to social programs that support jobs and communities in coal-mining areas in Ukraine. The price of Uranium oxide to Ukraine is not expected to deviate from trends in world market prices, which are expected to remain constant in real terms. The economic cost of this fuel includes an allowance for the cost of dealing with spent fuel. The economic cost of reclaiming schlamm from stock and transporting it to power stations is low in comparison to the cost of mined coal, and was taken to be around \$8/ton.

An important aspect of the data review was to set a range for the amount of residues from washed coal, known as schlamm, that would be available for use as boiler fuel. This low-quality fuel would only be useable in atmospheric fluidized bed combustion (AFBC) boilers because of its low calorific value, low volatile matter (in the anthracitic schlamm that is available) and very high sulfur and ash content. . After some discussion among those knowledgeable about the subject at the review meeting, it was agreed to adopt as a conservative assumption that 180 million tons of schlamm would be economically recoverable from the several hundred million tons currently on the ground in Ukraine. It was also agreed that this stock would increase at the rate of 10 million tons per year from current coal washing. At nominal consumption rates for 200 MW and 300 MW units, it was agreed that twenty existing generating units - ten of each size - could be repowered with AFBC boilers with adequate lifecycle fuel stocks of a 85%/15% schlamm/raw coal mix, based on the design of the new 200 MW AFBC boiler that is being installed at Unit 4 of Starobeshevo Power Station with EBRD financing.

The availability of existing nuclear units for service was reviewed during the data gathering phase of the analysis. It was agreed that the existing units are presently able to

¹ "Estimating Construction Costs and Schedules, Experience with Power Generation Projects in Developing Countries," World Bank Technical Paper No.325, Energy Series, 1996, pp. 23ff

sustain an availability level of 67%. There are upgrades in operating practice and hardware that are expected to be able to improve their availability to 75%. The improvements were estimated to cost US\$78 million per unit and would be applied to the VVER-1000 type units over a period of ten years. These improvements in plant availability are separate from the safety improvements that have been discussed for this reactor type. The improvements in availability were modeled to increase linearly over the ten year implementation period. As a measure of the value of these improvements, their cost effectiveness was also tested at a cost of US\$100 million per unit.

Appendix A contains tables showing the data used in the analysis.

D. Probabilities of Occurrence

Rather than seek a single, deterministic “forecast” based on a “most likely” value for each of the key planning variables, a probabilistic approach was adopted to deal with the broad range of possible values for these variables. Three values were selected for each variable that covered the range of possible values, designated High, Middle, and Low. This approach provides some insight on the likelihood of K2 and R4 being part of the least-cost power system development program under the uncertainty in making forecasts.

However, it is recognized that estimates of the future values of planning variables are subject to substantial uncertainty, which complicates attempts to assess the probability of their occurrence. The following four variables are critical for planning system development, and were used for defining the planning scenarios used in this analysis

- Annual system energy and peak demand
- Completion costs for K2 and R4
- Capital costs for rehabilitation of fossil-fuel generators
- Fuel costs

For the four variables, three were given probabilities of occurrence of 25%, 50% and 25% respectively for High, Middle and Low values. The fourth, K2 and R4 completion cost estimate, was given its own set of probabilities that are consistent with the distribution of actual costs to estimated cost that was used to derive the Middle and High values for the completion cost, namely 34% for the Low estimate, 40% for the Middle estimate, and 26% for the High estimate.

4. Analytical Process

The first steps of the analysis were to enter the planning information into the EGEAS computer model and test this information for accuracy. This test involved specifically including or excluding various power generation units to check their modeled performance against what was expected. All heat rates, fuel costs, non-fuel operating costs, capital costs, discount rates, etc. were checked by this process.

A check was conducted of the viability of the DSM programs included in the Hagler Bailly study. It was found that these programs were cost effective over a range of capital and operating costs. Therefore, approximately 500 MW of DSM programs were included as a fixed component of all the development programs analyzed, rather than incur the extensive additional computer time required to consider them as choices for optimization.

The economic case for the Dniester Pumped Storage Project to provide energy production/storage was specifically examined and found to be weak under all but the most extreme planning circumstances. This is explained by the Dniester Station's pumping/generation efficiency of 72% or 1.39 to 1, which is lower than the ratio of monthly on-peak cost to off-peak cost expected under future system circumstances. Therefore, the plant wouldn't be able to pay its operating and capital carrying costs out of profits from energy storage services. Hence, even though the plant may be valuable as a system control facility for such services to the grid operator as load following, energy settlement service, and frequency control, it was not considered as an option for capacity expansion in the analysis.

Tests of the value of the nuclear unit availability improvements at US\$78 million per unit showed a positive value. A slightly positive value was also found at US\$100 million per unit. Because of the computational burden of including these eleven units as choices in the optimization process, they were included as fixed improvements at the US\$78 million cost per unit unless a specific case called for them not to be used or to be used at some other cost.

Air pollution emissions rates were set up for each generating unit for sulfur dioxide, nitrous oxides and ash. The rates for sulfur dioxide and ash were based on the sulfur and ash content of the fuel. No sulfur removal equipment was known to exist for the present plants. Electrostatic precipitators (ESPs) for existing plants were assumed to operate at an average of 90% efficiency. Nitrous oxide emissions rates were estimated from typical values for the various types of units in the system. NO_x emissions are largely functions of combustion cycle and operating temperature. NO_x reduction equipment in the form of low-NO_x burners is known to be installed on only a small subset of the units in the Ukrainian system, so none were modeled.

Emissions reduction equipment was included to varying degrees in the rehabilitation or new plant cost proposals. For the high level rehabilitation option with AFBC boilers and

new units with AFBC boilers, sulfur dioxide removal was assumed to be 98% efficient. All rehabilitated and new units were assumed to have ESPs with 99% removal efficiency. Sulfur dioxide reduction for low and middle rehabilitated units was achieved by use of low sulfur washed coal. NO_x emission levels for all units were modeled as shown in the data tables.

Test cases were run to establish the air pollutant emissions rates for the system. The only comparative data available were system level emissions rates for sulfur dioxide, nitrous oxide and ash from the IEA report.² If the emissions totals found in the IEA report are scaled in proportion to the annual system energy, the emissions modeled approximate those from the report for sulfur dioxide and nitrous oxides. There is a difference in the ash emissions, possibly based on the assumption of higher efficiency of removal used in the IEA report (95%) than used in the current study.

Having established base conditions for the main analysis, a total of 185 optimization runs were performed to test all the planning scenarios, the decision risk profile, and other situations of interest. A total of 81 cases were devoted to direct analysis of the K2/R4 joint completion scenarios, and 16 more were performed for the sequential completion scenarios. Another 52 cases were run to test the decision risk profile. Three additional cases in the decision risk profile were calculated from other cases. The remaining 36 cases include tests of some extreme conditions and sensitivity of the outcomes to certain variable changes. These changes include tests of higher discount rates, extreme decline in demand for electricity, very low gas prices, and a test of breakeven K2/R4 completion costs. Some of the special cases were run to find the effect of a one-year delay in K2/R4 operation after completion due to delayed regulatory approval for operation, and if nuclear plant availability were to remain at 67% rather than improve to 75%.

A summary of the costs for all cases is given in Appendix B. The summary shows the scenario, the present value of all costs for the study period and total cost with extension period, and the least-cost in-service dates for K2 and R4. Appendix E shows the summary of the Base Case (all cost and performance variables at middle values) capital additions for all types of generation facilities through 2010.


² IEA, p.84; also "Ukraine, Suggested Priorities for Environmental Protection and Natural Resource Management," World Bank, Report No. 12238-UA, p. VI-6.

5. Results

A. Screening Curves

Screening curves were prepared using the base case planning scenario in order to obtain a preliminary indication of the ranking of the options for adding capacity to the Ukrainian power system, including the completion of K2 and R4. A screening curve represents the change in total generation cost per Megawatt-hour of electrical energy for a generating unit that results from an increase or decrease in the utilization of the capacity of the unit (the capacity factor). Total cost includes construction costs, fuel costs and non-fuel operating and maintenance costs. The curves were prepared using the middle level values for the key variables. The screening curves do not fully represent how a particular option would fit into a power system or how its use may be influenced by load growth. The screening curves are shown in Figure 1.

Figure 1



The main indication from the screening curves is that the cost of power at capacity factors above 50% is lowest from the completed K2 and R4 units, followed closely by high level rehabilitation of fossil fuel units through the replacement of original boilers by AFBC boilers to burn an 85%/15% mixture of schlamm and unwashed coal.

B. Base case scenario

In the base case scenario (all costs and performance choices at middle value), the joint completion of K2 and R4 in 2002 is part of the least-cost development program. K2 and R4 are the only additions to system supply capacity. The remainder of investments in supply capacity cover rehabilitation and upgrading of existing nuclear and fossil fuel plant. The least-cost development program is thus basically a rehabilitation program, not an expansion one.

K2 and R4 are needed as early as 2002 to substitute high cost energy produced from existing unrehabilitated fossil fuel plant, even though the present (1997) installed capacity is technically sufficient (but not economically the best) to supply system energy needs and peak load until around 2007.

Upgrading coal-fired plant with new AFBC boilers to burn a 85%/15% mixture of schlamm and raw coal is almost as economic for substituting high cost energy as completing K2 and R4.


In the least-cost development program, 5,000 MW of coal-fired capacity is upgraded with AFBC boilers by 2005, and 2,000 MW of similar capacity is rehabilitated to a low level subsequently by 2010.

Because of the combination of equipment age and the lack of maintenance of existing coal-fired boilers, and high fossil fuel costs, the reliability of system supply falls below the standard used for the analysis (Loss-of-Load-Probability of no more than 24 hours per year), and the cost of operation rises significantly without the investments in K2, R4 and AFBC boilers. This is seen by comparing the costs for Cases 23, 24, and 25 with Cases 2, 1, and 16, respectively in Appendix B.

C. Probability Analysis

Joint Completion


A total of 81 planning scenarios were analyzed to determine the range of least-cost installation dates for Khmelnitsky 2 and Rovno 4. Figure 2 presents graphically the probability that completion of both K2 and R4 by a particular year would be part of the least-cost power development program. The tabular information for Figure 2 is shown below it.



The potential also exists to complete K2 and R4 as a single completion project, but with a year or two between their service dates. This makes the distinction between joint completion and requiring completion of both units in the same year. The graph above for joint completion in the same year is based on the lower probability of least-cost timing between the two units, in this case R4.

The probabilities for each unit’s least-cost timing as part of a joint completion project is shown in Figure 3. These probabilities are based on the recognition that there may be a gap between the units’ service years. This consideration is carried through the rest of the probability analysis.

Figure 3




| Year | Khmelnitsky 2 | Rovno 4 |
|------|---------------|---------|
| 2002 | 70% | 50% |
| 2003 | 79% | 64% |
| 2004 | 84% | 66% |
| 2005 | 86% | 73% |
| 2006 | 93% | 79% |
| 2007 | 94% | 83% |
| 2008 | 99% | 86% |
| 2009 | 99% | 90% |
| 2010 | 100% | 93% |

To illustrate the relative importance of one of these variables in combination with the others, the differentiation of outcomes has been broken down by load growth scenario for further presentation.

The decision tree for each load growth rate is shown in Appendix C. For all scenarios (27), each tree shows the probability of occurrence, the present value of the system development program, and the least-cost completion dates for K2 and R4. Each branch of the load growth tree has its own set of probabilities for least-cost completion years for K2 and R4. These are shown in Figures 4, 5 and 6, for the Low, Middle and High Load Forecasts, respectively.

Figure 4




| Year | Khmelnitsky 2 | Rovno 4 |
|------|---------------|---------|
| 2002 | 56% | 26% |
| 2003 | 64% | 48% |
| 2004 | 79% | 57% |
| 2005 | 85% | 72% |
| 2006 | 90% | 76% |
| 2007 | 94% | 79% |
| 2008 | 98% | 84% |
| 2009 | 99% | 89% |
| 2010 | 100% | 94% |

For the Low Load Growth scenario K2 is more than 50 % likely to be part of the least-cost system development plan. The probability of K2 being in the least-cost plan increases relatively rapidly so that by 2010 it is fully likely to part of the least-cost development. R4 is less likely to be part of the least-cost plan under low load growth, the difference between its place in the least-cost plan coming from the additional cost of transmission. The 6% probability of R4 not being part of the least-cost plan up to 2010 comes from those situations of high R4 completion cost and low fuel cost.

The probability of the Low Load Forecast occurring is estimated to be 25%.

Figure 5




| Year | Khmelnitky 2 | Rovno 4 |
|------|--------------|---------|
| 2002 | 66% | 51% |
| 2003 | 79% | 64% |
| 2004 | 81% | 68% |
| 2005 | 84% | 72% |
| 2006 | 90% | 73% |
| 2007 | 92% | 81% |
| 2008 | 98% | 84% |
| 2009 | 99% | 88% |
| 2010 | 100% | 92% |

As in the low load growth scenario cases, K2 is fully likely to be part of the least-cost plan at some point in the study period. Because the load in this scenario is higher by 2002 than in the low case, the probability of K2 and R4 being part of the least-cost plan is higher in the early years than in the low case. However, the low load forecast, while dropping lower than the Middle forecast, does increase at a higher rate, and by 2010 is higher than the Middle forecast. Thus, R4 has a slightly lower probability of being part of the least-cost plan in 2010 than it would in the Low scenario.

The probability of the Middle load forecast occurring is estimated to be 50%.

Figure 6



| Year | Khmelnitsky 2 | Rovno 4 |
|------|---------------|---------|
| 2002 | 95% | 72% |
| 2003 | 97% | 79% |
| 2004 | 98% | 84% |
| 2005 | 99% | 89% |
| 2006 | 100% | 94% |
| 2007 | 100% | 94% |
| 2008 | 100% | 94% |
| 2009 | 100% | 94% |
| 2010 | 100% | 94% |

In the High load forecast scenarios, both K2 and R4 have high levels of probability to be part of the least-cost plan from their earliest possible completion dates. The plateau reached by both K2 and R4 probabilities of completion in 2006 indicates that for the given mix of costs for other options influencing the total operational cost, the units' potentials are realized early for the scenarios in which they are advantageous.

In general, the probabilities of timing for K2 and R4 being part of the least-cost plan are influenced within each load forecast scenario by the combination of the nuclear units' completion costs and the cost of gas used for co-firing the existing coal-fired boilers.

It is evident from the above graphs that there is a strong likelihood that completing K2 before 2010 would be part of the least-cost development program. Completing K2 in 2002 has better than an even chance of being part of the least-cost program. Completion of R4, while not as cost-effective as K2, has a very high probability of being part of the


joint completion least-cost program. There are circumstances in which R4 would not be least-cost, mostly in scenarios entailing a combination of very high completion costs and long-term low costs of natural gas. The analysis shows that by 2002 R4 has at least a 50% chance of being part of the least-cost program.

Sequential Completion

The sequential completion analyses considered the completion cost for R4 to follow the estimating case for K2. That is, if K2 was considered to have a middle value completion cost, then R4 would also have a middle value completion cost. This reduced the potential number of cases from 243 to 81. Tests of the system costs for sequential completion were made for scenarios in which K2/R4 completion cost, load forecast and fuel costs were varied. Fossil plant rehabilitation costs were held at their middle level in all scenarios tested. This reduced the number of scenarios to be analyzed from 81 to 27. This number of cases and the data selected are sufficient to provide a good insight to the effect of sequential completion.

With K2 completed in 2002, the least-cost completion year for Rovno 4 and its probability of occurrence are shown in Figure 7, with the tabular data following.

Figure 7



| Year | Rovno 4 |
|------|---------|
| 2005 | 74% |
| 2006 | 79% |
| 2010 | 94% |

There is close correlation in the least-cost timing for R4 between the joint and sequential completion approaches in the period beyond 2004, since the completion cost of K2 bears

all the differential between joint and sequential completion.

D. Decision Risk

The decisions to complete K2 and R4 jointly in 2002, or K2 and R4 sequentially, or not to complete them, inherently have the potential of being wrong, whichever one is made. Thus, it is important to know what the consequences of a decision to complete or not complete K2 and R4 are, whether jointly or sequentially, in addition to the probability of outcome for a correct choice.

Joint Completion

The cost risk associated with a decision to complete K2 and R4 in a particular year is the difference between the total economic cost of the least-cost development program with K2 and R4 completed in this year, and the total economic cost of the least-cost development program without this constraint. This cost risk is evaluated for each planning scenario. Likewise, the cost risk associated with a decision not to complete K2 and R4 is the difference between the total economic cost of the least-cost development program with K2 and R4 specifically excluded and the total economic cost of the least-cost development program without this constraint. A zero value for cost risk indicates that the decision is least-cost for the scenario.

The system total cost for each of the three decisions should be computed for the full range of planning scenarios. However, because of the relatively small effect of varying the cost of rehabilitating fossil fuel plant on the least-cost timing for completing K2 and R4, it was decided to use just the middle value for this variable in order to reduce the computational burden to approximately fifty scenarios.

The distribution of cost risk for these two decisions are shown in Table 1. Of the three key independent variables used to set the scenarios, the most influential on the least-cost timing for completing K2 and R4 appears to be their completion cost.

Table 1
Present Value Decision Cost Risk for Joint Completion
of Khmelnsky 2 and Rovno 4

| K2R4 Completion Cost | Fossil Fuel Prices | Power Demand Forecast | Cost Risk of K2R4 in 2002 | Cost Risk of no K2R4 | |
|----------------------------|--------------------------|-----------------------------|---------------------------------|----------------------------|-----|
| | | | (\$ million) | (\$ million) | |
| High | High | High | 9 | 248 | |
| | | Middle | 37 | 164 | |
| | | Low | 49 | 169 | |
| | Middle | Middle | High | 12 | 244 |
| | | | Middle | 41 | 119 |
| | | | Low | 56 | 158 |
| | Low | Low | High | 43 | 36 |
| | | | Middle | 121 | 21 |
| | | | Low | 149 | 20 |
| Middle | High | High | 0 | 501 | |
| | | Middle | 0 | 389 | |
| | | Low | 1 | 383 | |
| | Middle | Middle | High | 0 | 496 |
| | | | Middle | 0 | 340 |
| | | | Low | 1 | 366 |
| | Low | Low | High | 0 | 254 |
| | | | Middle | 22 | 184 |
| | | | Low | 41 | 174 |
| Low | High | High | 0 | 657 | |
| | | Middle | 0 | 546 | |
| | | Low | 0 | 537 | |
| | Middle | Middle | High | 0 | 652 |
| | | | Middle | 0 | 496 |
| | | | Low | 0 | 521 |
| | Low | Low | High | 0 | 410 |
| | | | Middle | 0 | 319 |
| | | | Low | 10 | 299 |
| AVERAGE COST RISK | | | 22 | 322 | |

In 15 of the 27 scenarios presented in Table 1, there is no or negligible cost risk of completing K2 and R4 in 2002, since that would be the timing under the least-cost program. All of these conditions come in scenarios in which the K2/R4 completion cost is a low or middle estimate. All of the high completion cost scenarios and three of the other completion cost scenarios carry a penalty for installing both K2 and R4 in 2002. The penalty for K2/R4 completion in 2002 rather than the least-cost year is relatively small for the cases other than with high completion cost, and all the other three occur under low fuel cost scenarios. The highest present value cost risk of a decision to complete K2 and R4 in 2002 is \$149 million, a scenario that includes high K2/R4 completion cost, low load forecast and low fuel cost. The average cost risk of early joint completion of K2 and R4

is \$22 million.

All of the no completion cases have a cost risk, which indicates that not to complete K2 and R4 is not least-cost in any of the scenarios. This cost risk ranges from a present value of \$20 million to one of \$657 million. The cost risk of deciding not to complete K2 and R4 when they could have been completed for middle value completion costs, and all other planning variables have their middle values, is \$340 million. The average cost risk of not completing K2 and R4 is \$322 million.

In comparing the relative cost risks, it is evident that the decision to complete K2 and R4 has a large advantage, even in some of the high completion cost scenarios. Only under circumstances of high completion costs and low fuel costs is there a relative advantage of not completing K2 and R4 compared to completing them in 2002. The largest decision advantage for not completing the units is \$129 million, compared to \$657 million for completing them. These results support the decision to complete K2 and R4 in 2002.

Sequential Completion

Analysis for the 27 planning scenarios of the cost of completing K2 and R4 sequentially shows that the present value cost of sequencing the completion of the two units averages \$114 million more than the cost with joint completion at the least-cost timing, and \$92 million more than joint completion in 2002, but \$208 million less than not completing K2 and R4. Hence, the decision to complete K2 and R4 in 2002 carries the lowest cost risk of the three decisions analyzed. The cost differentials of least-cost sequential completion versus least-cost joint completion, 2002 joint completion, and no completion of K2 and R4 are shown in Table 2.

Table 2
Present Value Decision Cost Risk for Sequential Completion
of Khmelnitsky 2 and Rovno 4

| K2R4 Completion Cost | Fossil Fuel Cost | Power Demand Forecast | Least-cost Sequential Completion versus | | | |
|----------------------------|------------------------|-----------------------------|---|---|----------------------------------|------|
| | | | Least-cost Joint Completion (\$ million) | 2002 Joint Completion (\$ million) | No Completion (\$ million) | |
| High | High | High | 113 | 104 | -135 | |
| | | Middle | 115 | 78 | -49 | |
| | | Low | 120 | 71 | -49 | |
| | Middle | Middle | High | 113 | 101 | -131 |
| | | | Middle | 98 | 57 | -21 |
| | | | Low | 122 | 66 | -36 |
| | Low | Low | High | 114 | 71 | 78 |
| | | | Middle | 141 | 20 | 120 |
| | | | Low | 155 | 6 | 135 |
| Middle | High | High | 115 | 115 | -386 | |
| | | Middle | 102 | 102 | -287 | |
| | | Low | 96 | 95 | -287 | |
| | Middle | Middle | High | 115 | 115 | -381 |
| | | | Middle | 100 | 100 | -240 |
| | | | Low | 94 | 93 | -272 |
| | Low | Low | High | 101 | 101 | -153 |
| | | | Middle | 92 | 70 | -92 |
| | | | Low | 97 | 56 | -77 |
| Low | High | High | 139 | 139 | -518 | |
| | | Middle | 127 | 127 | -419 | |
| | | Low | 118 | 118 | -419 | |
| | Middle | Middle | High | 139 | 139 | -513 |
| | | | Middle | 124 | 124 | -372 |
| | | | Low | 117 | 117 | -404 |
| | Low | Low | High | 125 | 125 | -285 |
| | | | Middle | 95 | 95 | -224 |
| | | | Low | 90 | 80 | -209 |
| AVERAGE COST RISK | | | 114 | 92 | -208 | |

D. Sensitivity Tests

The justification for completing K2 and R4 in 2002 on least-cost grounds was tested for sensitivity to changes in the values of the key planning variables. Each case analyzes the effect of a change in one of the variables, keeping the middle values for all the other variables. The cases for this analysis are included in the full set reported in Appendix B.

One sensitivity test examined the effect of using higher values for the cost of capital (the discount rate) than the base value of 10% real. The values tested were 13%, 16% and

20%. The results are shown in Cases 66, 64, and 65. These cases shows that all options are pushed out in time as the cost of capital increases: to 2003 for K2 and 2005 for R4 at 13%; 2006 and 2007, respectively at 16%; and 2007 and 2009, respectively at 20%. At 20%, K2 and R4 are the only major investments in the least-cost development program.

The break-even economic cost of completing K2 and R4 jointly at which the least-cost timing for completion remains at 2002 is approximately \$1490 million (Cases 61, 61A and 61B). A higher completion cost would delay the completion date under least-cost power system development. This break-even total cost is 26% higher than the "expected" middle value for joint completion cost. On the basis of the distribution for the ratio of actual cost to estimated cost that was used to derive the middle and high values for the completion cost, this break-even cost lies at a value which has a probability of between 75% and 80% of not being exceeded.

The least-cost timing of K2 and R4 could be affected by a major contraction of Ukrainian electricity demand that might be considered a possibility when large industrial consumers are obliged to pay fully in cash for their electricity consumption. This possibility was analyzed in Cases 60 and 70. In Case 60 the system load is assumed to stay at the low load forecast amount of 154,800 GWh for the remaining 10 years of the study, instead of rising to 223,500 GWh by 2010. Under these circumstances only K2 is selected as part of the least-cost program. The penalty for continued joint completion, shown in Case 60F, is \$53 million. In Case 70 the system load is assumed to drop in 2000 to 145,000 GWh. From that point, the load is assumed to grow at the same rate as in the low load forecast. In this case, the least-cost program includes completion of K2 in 2002 and R4 in 2005. Joint completion of both units in 2002 has a cost penalty of only \$13 million.

The extent to which the delivered cost of gas has to fall from the present level of \$2.65/GJ (\$2.40/GJ at the Ukrainian border) in order to displace the least-cost timing for completing K2 and R4 jointly from 2002 (for middle value K2/R4 completion costs) was also assessed. The results are shown in Cases 58 and 59, with delivered gas costs of \$1.80/GJ and \$2.00/GJ. Case 5 has gas costs between those for Cases 58 and 59, at \$1.92/GJ. In Case 59 K2 is optimally completed in 2002 and R4 in 2004. Higher gas costs would have both units completed in 2002. Both Cases 5 and 58 show least-cost completion of K2 in 2003 and R4 in 2005.

E. Emission Benefits of K2/R4

Total air pollution emissions for all the fossil fuel plant in the power system in the base case scenario (Case 2), and K2 and R4 completed in 2002, are compared with similar conditions but without K2 and R4 (Case 2N). The substantial differences in emission levels are the savings attributable to completing K2 and R4 in 2002, and are shown in Table 6.

Table 6
System Annual Air Pollution Emissions
Metric Tons

| YEAR | SO2 | | | NOX | | | ASH | | |
|------|---------------|------------------|---------|---------------|------------------|--------|---------------|------------------|--------|
| | With K2/R4 | Without K2/R4 | Diff. | With K2/R4 | Without K2/R4 | Diff. | With K2/R4 | Without K2/R4 | Diff. |
| 1997 | 1,177,899 | 1,177,899 | 0 | 300,461 | 300,461 | 0 | 1,038,820 | 1,038,820 | 0 |
| 1998 | 1,157,754 | 1,157,754 | 0 | 294,511 | 294,511 | 0 | 1,022,523 | 1,022,523 | 0 |
| 1999 | 1,127,826 | 1,127,826 | 0 | 285,826 | 285,826 | 0 | 997,469 | 997,469 | 0 |
| 2000 | 1,120,943 | 1,120,943 | 0 | 286,009 | 286,009 | 0 | 993,172 | 993,172 | 0 |
| 2001 | 1,193,871 | 1,193,871 | 0 | 306,668 | 306,668 | 0 | 1,044,564 | 1,044,564 | 0 |
| 2002 | 1,067,936 | 1,211,353 | 143,418 | 271,827 | 313,631 | 41,804 | 944,792 | 1,029,297 | 84,505 |
| 2003 | 1,113,810 | 1,165,883 | 52,073 | 285,105 | 311,056 | 25,951 | 973,233 | 1,013,431 | 40,197 |
| 2004 | 1,061,483 | 1,113,966 | 52,483 | 282,414 | 308,359 | 25,946 | 948,995 | 990,495 | 41,500 |
| 2005 | 1,011,906 | 1,108,233 | 96,327 | 280,136 | 314,955 | 34,819 | 923,802 | 964,995 | 41,193 |
| 2006 | 1,006,795 | 1,117,629 | 110,834 | 286,901 | 322,765 | 35,863 | 903,919 | 967,039 | 63,120 |
| 2007 | 1,047,717 | 1,071,299 | 23,582 | 301,750 | 321,300 | 19,550 | 902,582 | 951,088 | 48,506 |
| 2008 | 1,039,455 | 1,091,979 | 52,523 | 306,166 | 331,749 | 25,583 | 908,826 | 957,888 | 49,062 |
| 2009 | 1,033,020 | 1,138,433 | 105,413 | 311,239 | 347,073 | 35,834 | 915,908 | 973,850 | 57,942 |
| 2010 | 1,067,433 | 1,192,031 | 124,598 | 326,434 | 359,239 | 32,805 | 925,208 | 987,562 | 62,354 |

6. Conclusions

The evidence from this analysis shows that completion of Khmelniysky 2 and Rovno 4 in 2002 are likely to be part of Ukraine's least-cost long-term power development program, with a probability of 70% for K2 and 50% for R4. These probabilities rise rapidly each year until the probability is 100% for K2 and nearly 100% for R4 as the year 2010 is approached.

The probability assessment provides only a part of the picture, however. A more complete picture emerges by comparing the cost risk of a decision to complete K2 and R4 in 2002 versus delayed completion or no completion.

In 15 of the 27 main scenarios analyzed for Joint Completion, there is no or negligible cost risk of completing K2 and R4 in 2002, since this would be their timing of the least-cost program. All of these conditions come in scenarios in which the K2/R4 completion cost is at the low or middle level. All nine of the high joint completion cost scenarios and three other scenarios carry a higher cost for installing K2 and R4 in 2002, as compared to their completion at the ideal year in the least-cost plans for those scenarios. These penalties are relatively small for the non-high completion cost scenarios, and all three of these occur under low fuel cost scenarios. The highest present value cost risk of a decision to complete K2 and R4 in 2002 is \$149 million, a scenario that includes high K2/R4 completion cost, low load forecast, and low fuel costs. It should be noted, however, that there is still a \$20 million penalty in this scenario for not completing K2 and R4, even if the risk of too early installation is \$149 million. Thus, the net decision risk of this scenario for completing K2 and R4 in 2002 versus not completing them is \$129 million.

The average present value decision cost risk of completing K2 and R4 in 2002 versus the ideal timing is \$22 million.

Tests were made of all scenarios with K2 and R4 excluded. All of these scenarios have higher cost than the cost of completing the units at the least-cost timing. This indicates that some combination of completion of K2 and R4 is always better than not to complete them at all. The cost penalty of not completing K2 and R4 ranges from a present value of \$20 million to a high of \$657 million.

The analysis found the average cost risk of not completing K2 and R4 jointly is \$322 million.

Analysis for the 27 planning scenarios for sequential completion of K2 and R4 shows that the present value economic cost of their sequential completion averages \$114 million more than joint completion at the least-cost dates across the range of scenarios tested. The cost of sequential completion averages \$208 million less than the cost for not completing K2 and R4.

The cost of sequential completion averages \$92 million more than the cost of joint completion in 2002 across all scenarios tested.

Comparing the worst case net decision risk of \$129 million found in the table of Present Value Decision Cost Risk for Joint Completion with the \$92 million average cost penalty for the decision to sequence K2 and R4 completion, the cost difference is small. In all other scenarios the decision cost risk favors joint completion. Thus, it can be concluded that joint completion in 2002 is highly likely to be more cost effective than sequenced completion.

The analysis concludes that the decision to complete K2 and R4 in 2002 carries the highest economic advantage of the three decisions.

Sensitivity tests showed that the least-cost justification for the joint completion of K2 and R4 in 2002 is robust to changes in planning assumptions. Because of the generally poor condition of the bulk of the fossil-fueled generating capacity in Ukraine, many thousands of megawatts of existing coal-fired generation will require rehabilitation or replacement in the relatively near future. Once completed, K2 and R4 could provide cost-effective support for the system during an extensive and protracted program of rehabilitating fossil fuel capacity.

APPENDIX A
Data Tables

UKRAINE
K2/R4 Completion Due Diligence
Least Cost Planning Analysis
Energy Production and Peak Load Forecasts
Gross Generation Basis

| | Gross Annual Energy Generation (TWh) (Including Generators' Own Use) | | | Load Factor (%) | | Annual Peak Load (MW) | | | Annual Peak Load Growth Rates (%) | | | |
|-----------------|--|-----------------|---------------|------------------|-------|--------------------------|-----------------|---------------|--------------------------------------|-----------------|---------------|-----------------|
| | World Bank | | | High & Middle | Low | World Bank | | | World Bank | | | |
| | Middle (High) | Low (Middle) | EBRD (Low) | | | Middle (High) | Low (Middle) | EBRD (Low) | Middle (High) | Low (Middle) | EBRD (Low) | |
| | | | | | | | | | | | | |
| Actual | | | | | | | | | | | | Actual |
| 1993 | 227.2 | 227.2 | | | | 38,060 | 38,060 | 38,060 | | | | 1993 |
| 1994 | 200.6 | 200.6 | | | | 33,400 | 33,400 | 33,400 | | | | 1994 |
| 1995 | 189.8 | 189.8 | | | | 28,900 * | 28,900 | 28,900 * | | | | 1995 |
| 1996 | 179.4 | 179.4 | | | | 28,900 * | 28,900 | 28,900 * | | | | 1996 |
| Forecast | | | | | | | | | | | | Forecast |
| 1997 | 180.5 | 174.5 | 174.5 | 73.0% | 73.0% | 28,226 | 27,288 | 27,288 | | | | 1997 |
| 1998 | 181.9 | 173.0 | 162.7 | 72.4% | 72.4% | 28,687 | 27,283 | 25,659 | 1.63% | -0.02% | -5.97% | 1998 |
| 1999 | 184.8 | 170.8 | 157.1 | 71.8% | 71.8% | 29,394 | 27,167 | 24,988 | 2.47% | -0.43% | -2.61% | 1999 |
| 2000 | 191.2 | 172.8 | 154.8 | 71.2% | 71.2% | 30,675 | 27,723 | 24,835 | 4.36% | 2.05% | -0.61% | 2000 |
| 2001 | 197.6 | 175.1 | 159.9 | 70.5% | 70.5% | 31,978 | 28,337 | 25,877 | 4.25% | 2.22% | 4.20% | 2001 |
| 2002 | 204.2 | 177.6 | 166.2 | 69.9% | 69.9% | 33,337 | 28,995 | 27,134 | 4.25% | 2.32% | 4.85% | 2002 |
| 2003 | 210.9 | 182.8 | 173.1 | 69.3% | 69.3% | 34,737 | 30,109 | 28,511 | 4.20% | 3.84% | 5.08% | 2003 |
| 2004 | 217.7 | 188.1 | 180.1 | 68.7% | 68.7% | 36,178 | 31,259 | 29,930 | 4.15% | 3.82% | 4.98% | 2004 |
| 2005 | 224.7 | 193.6 | 187.3 | 68.1% | 68.1% | 37,679 | 32,464 | 31,408 | 4.15% | 3.85% | 4.94% | 2005 |
| 2006 | 231.4 | 199.2 | 195.2 | 67.5% | 67.5% | 39,156 | 33,708 | 33,031 | 3.92% | 3.83% | 5.17% | 2006 |
| 2007 | 238.5 | 205.0 | 203.1 | 66.8% | 66.8% | 40,729 | 35,008 | 34,684 | 4.02% | 3.86% | 5.00% | 2007 |
| 2008 | 245.9 | 210.9 | 211.3 | 66.2% | 66.2% | 42,383 | 36,351 | 36,420 | 4.06% | 3.83% | 5.00% | 2008 |
| 2009 | 253.4 | 217.1 | 219.7 | 65.6% | 65.6% | 44,086 | 37,770 | 38,223 | 4.02% | 3.91% | 4.95% | 2009 |
| 2010 | 260.9 | 223.5 | 228.2 | 65.0% | 65.0% | 45,820 | 39,252 | 40,077 | 3.93% | 3.92% | 4.85% | 2010 |

* - Peak loads in 1995 and 1996 limited by supply circumstances

Basis - World Bank Estimate updated as of 2/18/97 for energy and
Staff Appraisal Report on Ukraine Electricity Market Development Project Dated Sept. 16, 1996, Annex 1B, p.3 for load factor information

UKRAINE
K2/R4 Completion Due Diligence
Least Cost Planning Analysis

Khmelnitsky 2 and Rovno 4 Modeling Data

| | K2 + R4 | | | | K2 only | R4 only | | |
|--|----------|--------------|--------------|--------|---------|-----------------------------|---------|-------|
| | Completi | Decommission | Transmission | Total | Total | Completion + Decommissio | Transm. | Total |
| Capital Costs = Base Cost + Physical Contingencies - (\$ Millions) | | | | | | | | |
| Estimated cost | 869.4 | 47.3 | 67.0 | 983.7 | 550.0 | 458.3 | 67.0 | 525.3 |
| Expected cost | 1043.3 | 56.7 | 80.4 | 1180.4 | 660.0 | 550.0 | 80.4 | 630.4 |
| Upper limit cost | 1335.4 | 72.6 | 102.9 | 1510.9 | 844.8 | 704.0 | 102.9 | 806.9 |
| Heat Rate (KJ/kwh) | | | | | 11,000 | 11,000 | | |
| Fixed Operation & Maintenance Costs (\$/kw/year) | | | | | 30 | 30 | | |
| Variable Operation & Maintenance Costs (\$/Mwh) | | | | | 2.6 | 2.6 | | |
| Scheduled Maintenance (weeks/year) | | | | | 9 | 9 | | |
| Forced Outage Rate (%) | | | | | 7.7 | 7.7 | | |
| First Full Year of Operation | | | | | 2002 | 2002 | | |

Notes:

1. Cost Estimate is taken from consensus agreement reached on 4 Dec 97 by working group at Kiev data gathering meeting.
2. Initial fuel loading deducted from completion cost; fuel cost expressed in fuel cost rate for plant in which unit is located.
3. Completion costs are "overnight" construction costs.
4. Cost of transmission needs of \$67 million for R4 estimated cost is shown separately.
5. Expected cost equals Estimated cost (Base cost plus physical contingencies) times 1.2. It excludes price contingencies and IDC.
6. Upper limit cost (90% confidence level) equals Expected cost times 1.28.
7. Decommissioning cost estimated at 15% of the equivalent total capital cost of \$2,750/kW for constructing a "greenfield" nuclear power unit of the same design and capacity as K2 and R4, equal to \$412.5/kW, and incurred after thirty years of operation. Discounting this amount to the year of initial operation at 10% discount factor of 1/17.45) yields a cost as of the in-service date of \$23.64/kW, or \$23.64 million for each of K2 and R4. This cost is added to the completion cost to give the equivalent overall capital cost in economic terms as of the initial in-service date.

UKRAINE
K2/R4 Completion Due Diligence
Least Cost Planning Analysis
PLANNING DATA FOR EXISTING THERMAL PLANTS

RETIREMENT DATE OR END OF SERVICE LIFE

End of service at end of year
e

| Station Name | Unit Number | | | | | | | | | | | | | | |
|-------------------|-------------|------|------|------|------|------|------|------|------|------|------|----|----|----|----|
| | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 |
| Burshtyn 1-12 | 1999 | 2000 | 2001 | 2004 | | | | | | | | | | | |
| Dobrotvorsk 4-8 | | | | 1999 | 2000 | 2001 | 2002 | 2003 | | | | | | | |
| Krivoj Roj 1-10 | 2003 | 2005 | 2006 | 2004 | | | | | | | | | | | |
| Kurakov 3-9 | | | | | | | | | | | | | | | |
| Ladizhin 1-6 | | | | | | | | | | | | | | | |
| Lugansk 8-15 | | | | | | 1998 | 1999 | 2000 | 2000 | 2003 | 2004 | | | | |
| Mironov 1, 2 | 1998 | 1998 | | | | | | | | | | | | | |
| Pridneprovsk 7-14 | | | | | | | 1998 | 1999 | 2000 | 2002 | | | | | |
| Slavyansk 1, 2 | | | | | 1998 | | | | | | | | | | |
| Starobeshevo 4-13 | | | | 1996 | | | | | | | | | | | |
| Tripoli 1-6 | | | | | | | | | | | | | | | |
| Ulegorsk 1-7 | | | | | | | | | | | | | | | |
| Zaporozhe 1-7 | | | | | | | | | | | | | | | |
| Zmiev 1-10 | 2000 | | 2002 | | 2004 | | | | | | | | | | |
| Zuev 1-4 | | | | | | | | | | | | | | | |
| CHP Plants | | | | | | | | | | | | | | | |
| Kharkov 1-3 | | | | | | | | | | | | | | | |
| Kiev/5 1-4 | | | | | | | | | | | | | | | |
| Kiev/6 1,2 | | | | | | | | | | | | | | | |
| CHP 1-10 | | | | | | | | | | | | | | | |
| CHP 11-20 | | | | | | | | | | | | | | | |
| CHP 21-30 | | | | | | | | | | | | | | | |

Committed plant additions:
Starobeshevo Unit 4 210MW third level rehabilitation - in service by end-2000.
Zmiev Unit 8 300MW second level rehabilitation - in service by end-2000.

UKRAINE
K2/R4 Completion Due Diligence
Least Cost Planning Analysis

PLANNING DATA FOR EXISTING NUCLEAR PLANTS

| Unit | Rated Capacity (MW) | Operating Capacity (MW) | Heat Rate (KJ/KWh) | Fuel Cost (\$/GJ) | Fixed O&M (\$kW-Yr) | Variable O&M (\$/MWh) | Scheduled Maint. (Weeks) | Forced Outage (%) |
|-----------------|----------------------------|--------------------------------|---------------------------|--------------------------|--------------------------------|----------------------------------|---------------------------------|--------------------------|
| S. Ukraine - 1 | 1000 | 950 | 11,000 | 0.56 | 30 | 2.47 | 9 | 15.7% |
| S. Ukraine - 2 | 1000 | 950 | 11,000 | 0.56 | 30 | 2.47 | 9 | 15.7% |
| S. Ukraine - 3 | 1000 | 950 | 11,000 | 0.56 | 30 | 2.47 | 9 | 15.7% |
| Rovno - 1 | 402 | 361 | 11,000 | 0.56 | 30 | 2.47 | 8 | 3.0% |
| Rovno - 2 | 416 | 384 | 11,000 | 0.56 | 30 | 2.47 | 8 | 3.0% |
| Rovno - 3 | 1000 | 950 | 11,000 | 0.56 | 30 | 2.47 | 9 | 15.7% |
| Zaporozhe - 1 | 1000 | 950 | 11,000 | 0.56 | 30 | 2.47 | 9 | 15.7% |
| Zaporozhe - 2 | 1000 | 950 | 11,000 | 0.56 | 30 | 2.47 | 9 | 15.7% |
| Zaporozhe - 3 | 1000 | 950 | 11,000 | 0.56 | 30 | 2.47 | 9 | 15.7% |
| Zaporozhe - 4 | 1000 | 950 | 11,000 | 0.56 | 30 | 2.47 | 9 | 15.7% |
| Zaporozhe - 5 | 1000 | 950 | 11,000 | 0.56 | 30 | 2.47 | 9 | 15.7% |
| Zaporozhe - 6 | 1000 | 950 | 11,000 | 0.56 | 30 | 2.47 | 9 | 15.7% |
| Khmelnitzky - 1 | 1000 | 950 | 11,000 | 0.56 | 30 | 2.47 | 9 | 15.7% |

Chernobyl NPP shut down by end-2000.

UKRAINE
K2/R4 Completion Due Diligence
Least Cost Planning Analysis
PLANNING DATA FOR EXISTING THERMAL PLANTS

| Unit | 1st Unit Install Year | Rated Capacity (MW) | Operating Capacity (MW) | Full Load Heat Rate (KJ/KWh) | Fuel Type | Fixed O&M (\$kW-Yr) | Variable O&M (\$/MWh) | Scheduled Maint. (Weeks) | Forced Outage (%) |
|--------------------------|--------------------------------------|------------------------------------|--|---|----------------------|--|--|---|----------------------------------|
| Burshtyn (1-12) | 1965 | 2280 | 2075 | 9700 | Mix2 | 15 | 6.4 | 9 | 13.49% |
| Dobrotvor 3 (4-6) | 1959 | 300 | 276 | 14000 | Mix1 | 15.4 | 6.5 | 9 | 14.36% |
| Dobrotvor 2 (7-8) | 1963 | 300 | 276 | 14000 | Mix1 | 15.4 | 6.5 | 9 | 14.36% |
| Krivorozn | 1965 | 2820 | 2820 | 9738 | Mix1 | 12.4 | 5.9 | 9 | 20.75% |
| Kurakov | 1972 | 1470 | 1338 | 9842 | Mix1 | 16 | 6.1 | 9 | 13.50% |
| Ladizhin | 1970 | 1800 | 1638 | 9573 | Mix3 | 12.1 | 5.5 | 9 | 13.48% |
| Lugansk 8-15 | 1961 | 1600 | 1456 | 11141 | Mix3 | 15.9 | 7 | 9 | 13.48% |
| Lugansk 6,7 | 1956 | 200 | 182 | 14000 | Mix3 | 15.9 | 7 | 9 | 13.48% |
| Mironov 1 | | 100 | 55 | 14000 | Mix2 | 15 | 4 | 9 | 14.07% |
| Mironov 2 | | 200 | 182 | 14000 | Mix2 | 15 | 4 | 9 | 13.48% |
| Pridneprovsk 4-2 (7-10) | 1958 | 600 | 546 | 10004 | Mix2 | 15.9 | 6.2 | 9 | 20.75% |
| Pridneprovsk 4-1 (11-14) | 1963 | 1140 | 1037 | 9940 | Mix2 | 15.9 | 6.6 | 9 | 13.45% |
| Slavyansk 1 | | 800 | 800 | 9941 | Gas | 11.7 | 7.5 | 9 | 20.75% |
| Slavyansk 2 | | 200 | 185 | 14000 | Mix2 | 11.7 | 7.5 | 9 | 14.79% |
| Starobeshevo 4-13 | 1961 | 1750 | 1593 | 10400 | Mix2 | 15.8 | 7 | 9 | 23.19% |
| Tripoli 4 (1-4) | 1969 | 1200 | 1200 | 9522 | Mix2 | 12.3 | 5.5 | 9 | 20.75% |
| Tripoli 2 (5-6) | 1971 | 600 | 561 | 8870 | Oil | 14.6 | 7 | 9 | 15.64% |
| Ulegorsk 4 (1-4) | 1972 | 1200 | 1092 | 9163 | Mix1 | 12.6 | 5.5 | 9 | 13.48% |
| Ulegorsk 3 (5-7) | 1975 | 2400 | 2400 | 8787 | Oil | 11.7 | 7.5 | 9 | 20.75% |
| Zaporozhe 4 (1-4) | 1973 | 1200 | 1092 | 8973 | Mix2 | 12.6 | 5.5 | 9 | 13.48% |
| Zaporozhe 3 (5-7) | 1975 | 2400 | 2400 | 8874 | Gas | 8.3 | 5.5 | 9 | 20.75% |
| Zmiev 6 (1-6) | 1960 | 1050 | 955 | 10568 | Mix2 | 15.4 | 7 | 9 | 13.44% |
| Zmiev 4 (7-10) | 1965 | 1200 | 1100 | 9594 | Mix2 | 13.4 | 7.5 | 9 | 14.07% |
| Zuev | 1980 | 1200 | 1092 | 9241 | Mix1 | 12.6 | 5.5 | 9 | 13.48% |

| CHP PLANTS | | | | | | | | | |
|-------------------|------|------|-----|-------|------|------|------|---|--------|
| Kharkov 1,2 | | 206 | 206 | 11966 | Gas | 20.7 | 6.2 | 4 | 26.52% |
| Kharkov 3 | 1990 | 250 | 250 | 10281 | Gas | 14.7 | 6.7 | 4 | 29.58% |
| Kiev/5 1,2 | | 200 | 188 | 11921 | Mix5 | 19.6 | 6.7 | 4 | 25.09% |
| Kiev/5 3,4 | 1974 | 500 | 500 | 10265 | Mix5 | 14.8 | 6.7 | 4 | 29.58% |
| Kiev/6 1,2 | 1982 | 500 | 500 | 10265 | Mix5 | 14.8 | 6.7 | 4 | 29.58% |
| CHP 1-30 | | 1000 | 970 | 11966 | Gas | 32.9 | 15.2 | 7 | 19.25% |

Fuel Type: Mix1 - 85% Shtib, 15% Gas; Mix2 - 70% Shtib, 30% Gas; Mix 3- 50% Shtib, 50% Gas and Mazut;
 Mix 4- 70% Shtib, 30% Mazut; Mix5- 30% Mazut, 70% gas

**K2/R4 Ukraine Completion Due Diligence
Fuel Cost Escalation for High Fuel Cost Scenario**

| Fuel Type | Mix Ratios | | | Cost Basis | 1997 | 1998 | 1999 | 2000 | 2001 | 2002 | 2003 | 2004 | 2005 | 2006 | 2007 | 2008 | 2009 | 2010 |
|--------------------------|------------|------|---------|------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| | Schtib | Gas | Mazut | | | | | | | | | | | | | | | |
| Mix 1 | 85% | 15% | 0% | \$/GJ | 1.673 | 1.674 | 1.675 | 1.677 | 1.678 | 1.680 | 1.681 | 1.683 | 1.684 | 1.686 | 1.687 | 1.689 | 1.690 | 1.692 |
| | | | | \$/MBTU | 1.765 | 1.766 | 1.768 | 1.769 | 1.771 | 1.773 | 1.774 | 1.776 | 1.777 | 1.779 | 1.781 | 1.782 | 1.784 | 1.785 |
| | | | | %Chg | 0.088 | 0.088 | 0.088 | 0.088 | 0.089 | 0.089 | 0.089 | 0.089 | 0.090 | 0.090 | 0.090 | 0.090 | 0.090 | 0.091 |
| Mix 2 | 70% | 30% | 0% | \$/GJ | 1.845 | 1.848 | 1.851 | 1.854 | 1.857 | 1.860 | 1.863 | 1.866 | 1.869 | 1.872 | 1.875 | 1.878 | 1.881 | 1.884 |
| | | | | \$/MBTU | 1.947 | 1.950 | 1.953 | 1.956 | 1.959 | 1.962 | 1.966 | 1.969 | 1.972 | 1.975 | 1.978 | 1.982 | 1.985 | 1.988 |
| | | | | %Chg | 0.159 | 0.159 | 0.160 | 0.160 | 0.160 | 0.161 | 0.161 | 0.161 | 0.162 | 0.162 | 0.162 | 0.163 | 0.163 | |
| Mix 3 | 50% | 25% | 25% | \$/GJ | 2.118 | 2.120 | 2.122 | 2.125 | 2.127 | 2.130 | 2.132 | 2.135 | 2.137 | 2.140 | 2.142 | 2.145 | 2.147 | 2.150 |
| | | | | \$/MBTU | 2.234 | 2.237 | 2.240 | 2.242 | 2.245 | 2.247 | 2.250 | 2.253 | 2.255 | 2.258 | 2.261 | 2.263 | 2.266 | 2.269 |
| | | | | %Chg | 0.115 | 0.116 | 0.116 | 0.116 | 0.117 | 0.117 | 0.117 | 0.118 | 0.118 | 0.118 | 0.118 | 0.119 | 0.119 | |
| Mix 5 | 0% | 70% | 30% | \$/GJ | 2.701 | 2.708 | 2.715 | 2.722 | 2.729 | 2.735 | 2.742 | 2.749 | 2.756 | 2.764 | 2.771 | 2.778 | 2.785 | 2.792 |
| | | | | \$/MBTU | 2.850 | 2.857 | 2.865 | 2.872 | 2.879 | 2.886 | 2.894 | 2.901 | 2.909 | 2.916 | 2.924 | 2.931 | 2.939 | 2.946 |
| | | | | %Chg | 0.253 | 0.254 | 0.254 | 0.254 | 0.255 | 0.255 | 0.255 | 0.256 | 0.256 | 0.256 | 0.256 | 0.256 | 0.257 | 0.257 |
| Gas | 0% | 100% | 0% | \$/GJ | 2.650 | 2.660 | 2.670 | 2.679 | 2.689 | 2.699 | 2.709 | 2.719 | 2.729 | 2.739 | 2.749 | 2.760 | 2.770 | 2.780 |
| | | | | \$/MBTU | 2.796 | 2.807 | 2.817 | 2.827 | 2.838 | 2.848 | 2.859 | 2.869 | 2.880 | 2.891 | 2.901 | 2.912 | 2.923 | 2.933 |
| | | | | %Chg | 0.369 | 0.369 | 0.369 | 0.369 | 0.369 | 0.369 | 0.369 | 0.369 | 0.369 | 0.369 | 0.369 | 0.369 | 0.369 | 0.369 |
| Basic Fuel Costs - \$/GJ | | | | Esc. | | | | | | | | | | | | | | |
| | 1997 | 2010 | Rate | | | | | | | | | | | | | | | |
| Gas | 2.65 | 2.78 | 0.3691% | | | | | | | | | | | | | | | |
| Schtib | 1.50 | 1.50 | 0.00% | | | | | | | | | | | | | | | |
| Mazut | 2.82 | 2.82 | 0.00% | | | | | | | | | | | | | | | |

UKRAINE
K2/R4 Completion Due Diligence
Least Cost Planning Analysis

FUEL COSTS

| Fuel Type | Cost (\$/GJ) | Heat Content (KJ/kg) | Ash Content (%) | Sulfur Content (%) | Water Content (%) |
|---------------------------------------|-----------------------------|----------------------|-----------------|--------------------|-------------------|
| Schtib (Raw, Unwashed Coal) | 1.50 | 18,227 | 36 | 2.0 | 10 |
| Washed, Low sulfur Coal | 1.86 rising to 1.99 in 2010 | 21,160 | 25 | 1.2 | 10 |
| Gas - Scenario 1 | 2.65 | 33,520 | 0 | 0 | 0 |
| - Scenario 2 | 2.65 rising to 2.78 in 2010 | 33,520 | 0 | 0 | 0 |
| Mazut | 2.82 | 40,600 | 0 | 2.7 | 2 |
| Schlamm (Coal Washings) | 0.60 | 13,827 | 50 | 2.0 | 17 |
| Schlamm/Schtib Mix (85%/15%) | 0.74 | 14,487 | 48 | 2.0 | 16 |
| Mix 1 (85% Schtib/15% Gas) | 1.67 | 20,521 | 31 | 1.3 | N/A |
| Mix 2 (70% Schtib/30% Gas) | 1.85 | 22,815 | 25 | 1.4 | N/A |
| Mix 3 (50% Schtib/25% Gas, 25% Mazut) | 2.12 | 27,643 | 18 | 1.7 | N/A |
| Mix 4 (70% Schtib/30% Mazut) | 1.90 | 24,939 | 25 | 2.2 | N/A |
| Mix 5 (30% Mazut/70% Gas) | 2.70 | 35,644 | 0 | 0.8 | N/A |

Note - Quantities of fuel available:

| | |
|-------------|--|
| Washed Coal | unlimited |
| Schtib | unlimited |
| Schlamm | 180 million tons in 1997 plus 10 million tons/year |
| Tailings | 700 million tons |
| Mazut | unlimited |
| Gas | unlimited |

UKRAINE
K2/R4 Completion Due Diligence
Least Cost Planning Analysis
PLANNING DATA FOR EXISTING HYDRO PLANTS

| Plant Name | Operating Capacity (MW) | Annual Energy (Gwh) | Oper. & Maint. Costs | | Forced Outage Rate | Scheduled Maintenance (Weeks/year) | Operating Strategy |
|---------------------|-------------------------|---------------------|----------------------|-----------------|--------------------|------------------------------------|-----------------------|
| | | | Fixed \$/kw/year | Variable \$/MWh | | | |
| Kiev | 361 | 635 | 0 | 1.27 | 0.1% | None | Peaking |
| Kiev Pumped Storage | 235 | 114 | 0 | 1.44 | 0.1% | None | Peaking |
| Kanev | 235 | 850 | 0 | 1.21 | 0.1% | None | Intermediate, Peaking |
| Kremenchuk | 625 | 1506 | 0 | 0.76 | 0.1% | None | Intermediate, Peaking |
| Dnieprodzerzhink | 352 | 1250 | 0 | 0.54 | 0.1% | None | Intermediate, Peaking |
| Dnieper | 1515 | 4140 | 0 | 0.12 | 0.1% | None | Intermediate, Peaking |
| Kakhovka | 300 | 1420 | 0 | 0.38 | 0.1% | None | Intermediate, Peaking |
| Dniester | 702 | 800 | 0 | 0.91 | 0.1% | None | Peaking |
| Total | 4325 | 10715 | | | | | |

Note - Scheduled Maintenance performed so that it does not affect plant capacity factor, therefore shown as "None"

Note - For intermediate operation, peak reservoir filling in April and May, peak energy production in October November.

UKRAINE
K2/R4 Completion Due Diligence
Least Cost Planning Analysis

PLANNING DATA FOR REHABILITATED FOSSIL PLANTS

| Unit Type | Unit Size (MW) | | Capital Cost (\$/kw) | 1st Unit Install Year | Operating Life (Years) | Max. # Avail. | | Full Load Heat Rate (KJ/KWh) | Fuel Type | Fixed O&M (\$/kW/Yr) | Variable O&M (\$/MWh) | Scheduled Maint. (Weeks) | Forced Outage (%) | Install Outage Period |
|---------------------------|----------------|----------|----------------------|-----------------------|------------------------|---------------|-------|------------------------------|--------------|----------------------|-----------------------|--------------------------|-------------------|-----------------------|
| | Rated | Operatin | | | | Each Year | Total | | | | | | | |
| First Level Rehab. | 200 | 190 | 120 | 2000 | 15 | 4 | 7 | 9800 | Washed Coal | 15.00 | 5.50 | 6 | 8.5% | 4 Mo. |
| | 300 | 285 | 120 | 2000 | 15 | 4 | 4 | 9680 | Washed Coal | 12.00 | 5.00 | 6 | 8.5% | 4 Mo. |
| Second Level Reha | 200 | 205 | 400 | 2001 | 20 | 3 | 24 | 9570 | Washed Coal | 17.00 | 6.00 | 6 | 7.5% | 1 Year |
| | 300 | 310 | 350 | 2001 | 20 | 3 | 20 | 9430 | Washed Coal | 14.00 | 5.50 | 6 | 7.5% | 1 Year |
| Third Level Rehab. | 200 | 210 | 695 | 2001 | 25 | 2 | 10 | 9875 | Schtib/Schla | 17.00 | 6.50 | 6 | 7.0% | 2 Years |
| | 300 | 315 | 655 | 2001 | 25 | 2 | 10 | 9875 | Schtib/Schla | 14.00 | 6.50 | 6 | 7.0% | 2 Years |

First Level Rehab.- repairs, replace/repair ESP (Life of unit extended 15 years)

Second Level Rehab.- repairs, replace/repair ESP, new burners, arch firing, replace LP Turbine rotor (Life of unit extended 20 years)

Third Level Rehab. - repairs, new AFBC boiler, replace LP turbine rotor (Life of unit extended 25 years), then add \$60/kw after 10 years for undefined turbine/BOP needs

Units suitable for: First Level Rehab.- 7*200 MW at Kurakhov; 4*300 MW units at Zuev.

200 MW Units suitable for Second or Third Level Rehab. - Bushtyn - 12, Lugansk - 8, Starobeshevo -9, Zmiev - 6; total = 35

300 MW Units suitable for Second or Third Level Rehab - Kiev/5 - 2 (mid only), Kiev/6 - 2 (mid only), Krivoj Roy - 9, Ladyzhinsk - 6,

Pridneprovsk - 4, Tripolie - 4, Ulegorsk - 4, Zaporozhe - 4, Zmiev - 4; total = 39

PLANNING DATA FOR NEW FOSSIL PLANTS

| Unit Type | Unit Size (MW) | | Capital Cost (\$/kw) | 1st Unit Install Year | Operating Life (Years) | Max. # Avail. | | Full Load Heat Rate (KJ/KWh) | Fuel Type | Fixed O&M (\$/kW/Yr) | Variable O&M (\$/MWh) | Scheduled Maint. (Weeks) | Forced Outage (%) |
|-----------------------------------|----------------|----------|----------------------|-----------------------|------------------------|---------------|-------|------------------------------|----------------------|----------------------|-----------------------|--------------------------|-------------------|
| | Rated | Operatin | | | | Each Year | Total | | | | | | |
| Combined Cycle | 300 | 315 | 750 | 2001 | 30 | 6 | N/A | 7570 | Gas | 7.00 | 3.00 | 4 | 7.0% |
| Combustion Turbine | 119 | 119 | 375 | 2000 | 30 | 5 | N/A | 11097 | Gas | 3.50 | 1.50 | 2 | 6.0% |
| Atmospheric Fluidized Bed | 300 | 315 | 1250 | 2002 | 35 | 6 | N/A | 9875 | Schtib/Schlamm | 12.50 | 6.00 | 6 | 7.0% |
| Dniester Pumped Storage(*) | 7 X 324 | 2268 | 437 | 2000 | 50 | 3 | 7 | N/A | 72% Cycle Efficiency | 6.00 | 1.00 | 4 | 0.1% |

Note - Dniester Pumped Storage Project annual energy generation - 810 GWh per 324 MW unit

UKRAINE
K2/R4 Completion Due Diligence
Least Cost Planning Analysis

NOX ENVIRONMENTAL PLANNING DATA FOR FOSSIL PLANTS
(ALL UNIT TYPES)

| | Heat Rate (btu/kwh) | NOX | |
|---------------------------|------------------------|--------------------------------|------------|
| | | Emission Rate (*) (lb/Mbtu) | (Tons/Gwh) |
| Existing | | | |
| 150 - 300 MW Coal | 9500 | 0.800 | 3.45 |
| 720 - 800 MW Gas | 9350 | 0.250 | 1.06 |
| 300 - 800 MW Oil | 9350 | 0.600 | 2.55 |
| Rehabilitated | | | |
| 200 - 300 MW Low Level | 9200 | 0.800 | 3.35 |
| 200 - 300 MW Mid Level | 9000 | 0.400 | 1.64 |
| 200 - 300 MW High Level | 9350 | 0.300 | 1.28 |
| New | | | |
| 300 MW Combined Cycle | 7172 | 0.030 | 0.10 |
| 119 MW Combustion Turbine | 10517 | 0.090 | 0.43 |
| 300 MW CFB | 9350 | 0.300 | 1.28 |

(*) - NOX Emission Rate is in metric tons

Sources -

Existing and low level rehab - Table 2 (U.S. EPA AP-42 Emissions Factors) and Table 3 (API Emission Factors from Petroleum Industry Equipment) in "Title 1 - Ozone Attainment through NOX Control Strategies", Stephen C. Wood, AIChE 1992 Summer national Meeting, Session 64.

New and other rehab - "Development of Engineering, Cost, and Performance Data for Generation Supply Options for New England, Stone & Webster Engineering Corp. Final Report, February 1993.

UKRAINE
Khmelnitsky 2 and Rovno 4 Completion Due Diligence
Least Cost Planning Analysis

Capital Expenditure Patterns of "Overnight Cost"
and
Conflated Completion Cost Multipliers

| Year | Percent Expended | Year "0" Cost Multiplier at Various Discount Rates | | | |
|--|------------------|--|--------|--------|--------|
| | | 10% | 13% | 16% | 20% |
| Khmelnitsky 2 and Rovno 4 | | | | | |
| -3 | 39.10 | 49.62 | 53.07 | 56.67 | 61.68 |
| -2 | 30.10 | 34.73 | 36.16 | 37.61 | 39.57 |
| -1 | 15.30 | 16.05 | 16.26 | 16.48 | 16.76 |
| 0 | 6.60 | 6.29 | 6.21 | 6.13 | 6.02 |
| +1 | 3.40 | 2.95 | 2.83 | 2.72 | 2.59 |
| +2 | 3.40 | 2.68 | 2.50 | 2.35 | 2.16 |
| +3 | 2.10 | 1.50 | 1.37 | 1.25 | 1.11 |
| Total | 100.00 | 113.82 | 118.41 | 123.19 | 129.88 |
| High Level Fossil Rehab and New AFBC | | | | | |
| -3 | 24.00 | 30.46 | 32.58 | 34.78 | 37.86 |
| -2 | 49.00 | 56.53 | 58.86 | 61.22 | 64.41 |
| -1 | 19.00 | 19.93 | 20.20 | 20.46 | 20.81 |
| 0 | 8.00 | 7.63 | 7.53 | 7.43 | 7.30 |
| Total | 100.00 | 114.54 | 119.16 | 123.89 | 130.39 |
| Middle Level Fossil Rehab | | | | | |
| -2 | 50.00 | 57.68 | 60.06 | 62.47 | 65.73 |
| -1 | 50.00 | 52.44 | 53.15 | 53.85 | 54.77 |
| Total | 100.00 | 110.12 | 113.21 | 116.32 | 120.50 |
| Low Level Fossil Rehab and Combustion Turbine | | | | | |
| -1 | 100.00 | 104.88 | 106.30 | 107.70 | 109.54 |
| Combined Cycle | | | | | |
| -3 | 20.00 | 25.38 | 27.15 | 28.99 | 31.55 |
| -2 | 50.00 | 57.68 | 60.06 | 62.47 | 65.73 |
| -1 | 30.00 | 31.46 | 31.89 | 32.31 | 32.86 |
| Total | 100.00 | 114.53 | 119.10 | 123.76 | 130.14 |

UKRAINE
Khmelnytsky 2 and Rovno 4 Completion Due Diligence

Least Cost Planning Analysis

In-Service Date Capital Costs (US\$/kW)

| % Cost of Capital- | 10.00% | | Overnight | Present Value | Overnight | Transm. Cost | In-Service Date Capital Cost |
|-------------------------------|--------|------------|----------------------|--|--------------------------|-----------------|---------------------------------------|
| | | | Construction Cost | Decommissioning or Other Delayed Costs | + Other Plant Cost | | |
| Khmelnytsky | 2 | | | | | | |
| | Low | Joint | 434.70 | 23.64 | 458.3 | | 518.4 |
| | | Sequential | 526.36 | 23.64 | 550.0 | | 622.7 |
| | Middle | Joint | 521.63 | 28.37 | 550.0 | | 622.1 |
| | | Sequential | 631.63 | 28.37 | 660.0 | | 747.3 |
| | High | Joint | 667.69 | 36.31 | 704.0 | | 796.2 |
| | | Sequential | 808.49 | 36.31 | 844.8 | | 956.5 |
| Rovno | 4 | | | | | | |
| | Low | Joint | 434.70 | 23.64 | 458.3 | 67.0 | 585.4 |
| | | Sequential | 434.70 | 23.64 | 458.4 | 67.0 | 585.4 |
| | Middle | Joint | 521.65 | 28.37 | 550.0 | 80.4 | 702.5 |
| | | Sequential | 521.65 | 28.37 | 550.0 | 80.4 | 702.5 |
| | High | Joint | 667.71 | 36.31 | 704.0 | 102.9 | 899.2 |
| | | Sequential | 667.71 | 36.31 | 704.0 | 102.9 | 899.2 |
| Fossil High Rehab | | | | | | | |
| | Low | 200 MW | 579.00 | 23.13 | 602.1 | | 686.3 |
| | | 300 MW | 546.00 | 23.13 | 569.1 | | 648.5 |
| | Middle | 200 MW | 695.00 | 23.13 | 718.1 | | 819.2 |
| | | 300 MW | 655.00 | 23.13 | 678.1 | | 773.4 |
| | High | 200 MW | 834.00 | 23.13 | 857.1 | | 978.4 |
| | | 300 MW | 786.00 | 23.13 | 809.1 | | 923.4 |
| Fossil Middle Rehab | | | | | | | |
| | Low | 200 MW | 333.00 | | 333.0 | | 366.7 |
| | | 300 MW | 292.00 | | 292.0 | | 321.6 |
| | Middle | 200 MW | 400.00 | | 400.0 | | 440.5 |
| | | 300 MW | 350.00 | | 350.0 | | 385.4 |
| | High | 200 MW | 480.00 | | 480.0 | | 528.6 |
| | | 300 MW | 420.00 | | 420.0 | | 462.5 |
| Fossil Low Rehab | | | | | | | |
| | Low | 200 MW | 100.00 | | 100.0 | | 104.9 |
| | | 300 MW | 100.00 | | 100.0 | | 104.9 |
| | Middle | 200 MW | 120.00 | | 120.0 | | 125.9 |
| | | 300 MW | 120.00 | | 120.0 | | 125.9 |
| | High | 200 MW | 144.00 | | 144.0 | | 151.0 |
| | | 300 MW | 144.00 | | 144.0 | | 151.0 |
| Combustion Turbine | | | 375.00 | | 375.0 | | 393.3 |
| Combined Cycle | | | 750.00 | | 750.0 | | 859.0 |
| New Coal-fired Unit with AFBC | | | 1250.00 | | 1250.0 | | 1431.8 |

UKRAINE
Khmelnitsky 2 and Rovno 4 Completion Due Diligence
Least Cost Planning Analysis

| % Cost of Capital- | In-Service Date Capital Costs (US\$/kW) | | | | | | |
|-------------------------------|---|--|-----------------------------------|---|---------------------------------------|-----------------|---------------------------------------|
| | 13.00% | | Overnight Construction Cost | Present Value Decommissioning or Other Delayed Costs | Overnight + Other Plant Cost | Transm. Cost | In-Service Date Capital Cost |
| Khmelnitsky 2 | | | | | | | |
| Low | Joint | | 434.70 | 10.55 | 445.2 | | 525.3 |
| | Sequential | | 526.36 | 10.55 | 536.9 | | 633.8 |
| Middle | Joint | | 521.63 | 12.65 | 534.3 | | 630.3 |
| | Sequential | | 631.63 | 12.65 | 644.3 | | 760.5 |
| High | Joint | | 667.69 | 16.20 | 683.9 | | 806.8 |
| | Sequential | | 808.49 | 16.20 | 824.7 | | 973.5 |
| Rovno 4 | | | | | | | |
| Low | Joint | | 434.70 | 10.55 | 445.2 | 67.0 | 592.3 |
| | Sequential | | 434.70 | 10.55 | 445.2 | 67.0 | 592.3 |
| Middle | Joint | | 521.65 | 12.65 | 534.3 | 80.4 | 710.7 |
| | Sequential | | 521.65 | 12.65 | 534.3 | 80.4 | 710.7 |
| High | Joint | | 667.71 | 16.20 | 683.9 | 102.9 | 909.7 |
| | Sequential | | 667.71 | 16.20 | 683.9 | 102.9 | 909.7 |
| Fossil High Rehab | | | | | | | |
| Low | 200 MW | | 579.00 | 17.68 | 596.7 | | 707.6 |
| | 300 MW | | 546.00 | 17.68 | 563.7 | | 668.3 |
| Middle | 200 MW | | 695.00 | 17.68 | 712.7 | | 845.8 |
| | 300 MW | | 655.00 | 17.68 | 672.7 | | 798.2 |
| High | 200 MW | | 834.00 | 17.68 | 851.7 | | 1011.5 |
| | 300 MW | | 786.00 | 17.68 | 803.7 | | 954.3 |
| Fossil Middle Rehab | | | | | | | |
| Low | 200 MW | | 333.00 | | 333.0 | | 377.0 |
| | 300 MW | | 292.00 | | 292.0 | | 330.6 |
| Middle | 200 MW | | 400.00 | | 400.0 | | 452.8 |
| | 300 MW | | 350.00 | | 350.0 | | 396.2 |
| High | 200 MW | | 480.00 | | 480.0 | | 543.4 |
| | 300 MW | | 420.00 | | 420.0 | | 475.5 |
| Fossil Low Rehab | | | | | | | |
| Low | 200 MW | | 100.00 | | 100.0 | | 106.3 |
| | 300 MW | | 100.00 | | 100.0 | | 106.3 |
| Middle | 200 MW | | 120.00 | | 120.0 | | 127.6 |
| | 300 MW | | 120.00 | | 120.0 | | 127.6 |
| High | 200 MW | | 144.00 | | 144.0 | | 153.1 |
| | 300 MW | | 144.00 | | 144.0 | | 153.1 |
| Combustion Turbine | | | 375.00 | | 375.0 | | 398.6 |
| Combined Cycle | | | 750.00 | | 750.0 | | 893.2 |
| New Coal-fired Unit with AFBC | | | 1250.00 | | 1250.0 | | 1489.5 |

UKRAINE

Khmelnitsky 2 and Rovno 4 Completion Due Diligence

Least Cost Planning Analysis

In-Service Date Capital Costs (US\$/kW)

| % Cost of Capital- | | 16.00% | | Present Value Decommissioning or Other Delayed Costs | Overnight + Other Plant Cost | Transm. Cost | In-Service Date Capital Cost |
|-------------------------------|------------|--------|-----------------------------------|---|---------------------------------------|-----------------|---------------------------------------|
| | | | Overnight Construction Cost | | | | |
| Khmelnitsky 2 | | | | | | | |
| Low | Joint | | 434.70 | 4.80 | 439.5 | | 540.3 |
| | Sequential | | 526.36 | 4.80 | 531.2 | | 653.3 |
| Middle | Joint | | 521.63 | 5.77 | 527.4 | | 648.4 |
| | Sequential | | 631.63 | 5.77 | 637.4 | | 783.9 |
| High | Joint | | 667.69 | 7.38 | 675.1 | | 829.9 |
| | Sequential | | 808.49 | 7.38 | 815.9 | | 1003.4 |
| Rovno 4 | | | | | | | |
| Low | Joint | | 434.70 | 4.80 | 439.5 | 67.0 | 607.3 |
| | Sequential | | 434.70 | 4.80 | 439.5 | 67.0 | 607.3 |
| Middle | Joint | | 521.65 | 5.77 | 527.4 | 80.4 | 728.8 |
| | Sequential | | 521.65 | 5.77 | 527.4 | 80.4 | 728.8 |
| High | Joint | | 667.71 | 7.38 | 675.1 | 102.9 | 932.9 |
| | Sequential | | 667.71 | 7.38 | 675.1 | 102.9 | 932.9 |
| Fossil High Rehab | | | | | | | |
| Low | 200 MW | | 579.00 | 13.60 | 592.6 | | 730.9 |
| | 300 MW | | 546.00 | 13.60 | 559.6 | | 690.1 |
| Middle | 200 MW | | 695.00 | 13.60 | 708.6 | | 874.7 |
| | 300 MW | | 655.00 | 13.60 | 668.6 | | 825.1 |
| High | 200 MW | | 834.00 | 13.60 | 847.6 | | 1046.9 |
| | 300 MW | | 786.00 | 13.60 | 799.6 | | 987.4 |
| Fossil Middle Rehab | | | | | | | |
| Low | 200 MW | | 333.00 | | 333.0 | | 387.3 |
| | 300 MW | | 292.00 | | 292.0 | | 339.7 |
| Middle | 200 MW | | 400.00 | | 400.0 | | 465.3 |
| | 300 MW | | 350.00 | | 350.0 | | 407.1 |
| High | 200 MW | | 480.00 | | 480.0 | | 558.3 |
| | 300 MW | | 420.00 | | 420.0 | | 488.5 |
| Fossil Low Rehab | | | | | | | |
| Low | 200 MW | | 100.00 | | 100.0 | | 107.7 |
| | 300 MW | | 100.00 | | 100.0 | | 107.7 |
| Middle | 200 MW | | 120.00 | | 120.0 | | 129.2 |
| | 300 MW | | 120.00 | | 120.0 | | 129.2 |
| High | 200 MW | | 144.00 | | 144.0 | | 155.1 |
| | 300 MW | | 144.00 | | 144.0 | | 155.1 |
| Combustion Turbine | | | 375.00 | | 375.0 | | 403.9 |
| Combined Cycle | | | 750.00 | | 750.0 | | 928.2 |
| New Coal-fired Unit with AFBC | | | 1250.00 | | 1250.0 | | 1548.7 |

UKRAINE
Khmelnitsky 2 and Rovno 4 Completion Due Diligence
Least Cost Planning Analysis

| % Cost of Capital- | | In-Service Date Capital Costs (US\$/kW) | | | | | In-Service Date Capital Cost |
|-------------------------------|--------|---|-----------------------------|--|------------------------------|--------------|------------------------------|
| | | 20.00% | Overnight Construction Cost | Present Value Decommissioning or Other Delayed Costs | Overnight + Other Plant Cost | Transm. Cost | |
| Khmelnitsky 2 | Low | Joint | 434.70 | 1.74 | 436.4 | | 566.3 |
| | | Sequential | 526.36 | 1.74 | 528.1 | | 685.4 |
| | Middle | Joint | 521.63 | 2.09 | 523.7 | | 679.6 |
| | | Sequential | 631.63 | 2.09 | 633.7 | | 822.5 |
| | High | Joint | 667.69 | 2.67 | 670.4 | | 869.9 |
| | | Sequential | 808.49 | 2.67 | 811.2 | | 1052.8 |
| Rovno 4 | Low | Joint | 434.70 | 1.74 | 436.4 | 67.0 | 633.3 |
| | | Sequential | 434.70 | 1.74 | 436.4 | 67.0 | 633.3 |
| | Middle | Joint | 521.65 | 2.09 | 523.7 | 80.4 | 760.0 |
| | | Sequential | 521.65 | 2.09 | 523.7 | 80.4 | 760.0 |
| | High | Joint | 667.71 | 2.67 | 670.4 | 102.9 | 972.8 |
| | | Sequential | 667.71 | 2.67 | 670.4 | 102.9 | 972.8 |
| Fossil High Rehab | Low | 200 MW | 579.00 | 9.69 | 588.7 | | 764.6 |
| | | 300 MW | 546.00 | 9.69 | 555.7 | | 721.6 |
| | Middle | 200 MW | 695.00 | 9.69 | 704.7 | | 915.9 |
| | | 300 MW | 655.00 | 9.69 | 664.7 | | 863.7 |
| | High | 200 MW | 834.00 | 9.69 | 843.7 | | 1097.1 |
| | | 300 MW | 786.00 | 9.69 | 795.7 | | 1034.5 |
| Fossil Middle Rehab | Low | 200 MW | 333.00 | | 333.0 | | 401.3 |
| | | 300 MW | 292.00 | | 292.0 | | 351.9 |
| | Middle | 200 MW | 400.00 | | 400.0 | | 482.0 |
| | | 300 MW | 350.00 | | 350.0 | | 421.7 |
| | High | 200 MW | 480.00 | | 480.0 | | 578.4 |
| | | 300 MW | 420.00 | | 420.0 | | 506.1 |
| Fossil Low Rehab | Low | 200 MW | 100.00 | | 100.0 | | 109.5 |
| | | 300 MW | 100.00 | | 100.0 | | 109.5 |
| | Middle | 200 MW | 120.00 | | 120.0 | | 131.5 |
| | | 300 MW | 120.00 | | 120.0 | | 131.5 |
| | High | 200 MW | 144.00 | | 144.0 | | 157.7 |
| | | 300 MW | 144.00 | | 144.0 | | 157.7 |
| Combustion Turbine | | 375.00 | | 375.0 | | 410.8 | |
| Combined Cycle | | 750.00 | | 750.0 | | 976.0 | |
| New Coal-fired Unit with AFBC | | 1250.00 | | 1250.0 | | 1629.8 | |

APPENDIX B
Case Summaries

**Khmelnitsky 2 and Rovno 4 Completion Due Diligence
Least Cost Planning Analysis
Case Summary**

| Case No. | Load Level | Options Description | | | | | | | PVRR Results(\$M) | | K2/R4 Status | |
|----------|------------|---------------------|-------------------|------------------|--------------------|------------------|------------------|-----------------------------|-------------------|----------------|----------------|----------------|
| | | K2/R4 Completion | Fossil Rehab Cost | Fossil Fuel Cost | New AFCB Available | New CC Available | New CT Available | Nuclear Avail. Upgrade Cost | Through 2010 | With Extension | K2 | R4 |
| 1 | WB Middle | Middle | Middle | Middle | Yes | Yes | Yes | Low | 37,300 | 54,728 | 2002 | 2002 |
| 1N | WB Middle | Forced Out | Middle | Middle | Yes | Yes | Yes | Low | 37,537 | 55,224 | Forced Out | Forced Out |
| 2 | WB Low | Middle | Middle | Middle | Yes | Yes | Yes | Low | 32,117 | 46,018 | 2002 | 2002 |
| 2N | WB Low | Forced Out | Middle | Middle | Yes | Yes | Yes | Low | 32,250 | 46,358 | Forced Out | Forced Out |
| 3 | WB Low | Middle | Middle | Middle | Yes | Yes | Yes | High | 32,183 | 46,132 | 2002 | 2002 |
| 3N | WB Low | Forced Out | Middle | Middle | Yes | Yes | Yes | High | 32,317 | 46,472 | Forced Out | Forced Out |
| 4 | WB Low | Middle | Middle | Middle | Yes | Yes | Yes | Not Available | 32,077 | 46,140 | 2002 | 2002 |
| 4N | WB Low | Forced Out | Middle | Middle | Yes | Yes | Yes | Not Available | 32,223 | 46,533 | Forced Out | Forced Out |
| 5 | WB Low | Middle | Middle | Low | Yes | Yes | Yes | Low | 30,672 | 44,028 | 2003 | 2005 |
| 5F | WB Low | Middle | Middle | Low | Yes | Yes | Yes | Low | 30,693 | 44,050 | Forced in 2002 | Forced in 2002 |
| 5N | WB Low | Forced Out | Middle | Low | Yes | Yes | Yes | Low | 30,745 | 44,212 | Forced Out | Forced Out |
| 6 | WB Low | Middle | Low | Middle | Yes | Yes | Yes | Low | 31,967 | 45,670 | 2002 | 2003 |
| 6F | WB Low | Middle | Low | Middle | Yes | Yes | Yes | Low | 31,968 | 45,671 | Forced in 2002 | Forced in 2002 |
| 6N | WB Low | Forced Out | Low | Middle | Yes | Yes | Yes | Low | 32,057 | 45,956 | Forced Out | Forced Out |
| 7 | WB Low | High | Middle | Middle | Yes | Yes | Yes | Low | 32,231 | 46,239 | 2006 | 2010 |
| 7F | WB Low | High | Middle | Middle | Yes | Yes | Yes | Low | 32,271 | 46,280 | Forced in 2002 | Forced in 2002 |
| 7N | WB Low | Forced Out | Middle | Middle | Yes | Yes | Yes | Low | 32,250 | 46,358 | Forced Out | Forced Out |
| 8 | WB Low | Middle | High | Middle | Yes | Yes | Yes | Low | 32,210 | 46,335 | 2002 | 2002 |
| 8N | WB Low | Forced Out | High | Middle | Yes | Yes | Yes | Low | 32,398 | 46,749 | Forced Out | Forced Out |
| 9 | WB Low | Middle | Low | Low | Yes | Yes | Yes | Low | 30,600 | 43,784 | 2003 | 2007 |

| | | | | | | | | | | | | |
|---------------|-----------|------------|---------------|--------|-----|-----|-----|-----|------------------|--------|----------------|----------------|
| 9F | WB Low | Middle | Low | Low | Yes | Yes | Yes | Low | 30,624 | 43,808 | Forced in 2002 | Forced in 2002 |
| 9N | WB Low | Forced Out | Low | Low | Yes | Yes | Yes | Low | 30,635 | 43,906 | Forced Out | Forced Out |
| 10 | WB Low | High | Low | Low | Yes | Yes | Yes | Low | 30,634 | 43,890 | 2010 | Not Installed |
| 10F | WB Low | High | Low | Low | Yes | Yes | Yes | Low | 30,779 | 44,071 | Forced in 2002 | Forced in 2002 |
| 10N | WB Low | Forced Out | Low | Low | Yes | Yes | Yes | Low | 30,635 | 43,906 | Forced Out | Forced Out |
| 11 | WB Low | High | High | Middle | Yes | Yes | Yes | Low | 32,346 | 46,579 | 2003 | 2007 |
| 11F | WB Low | High | High | Middle | Yes | Yes | Yes | Low | 32,364 | 46,597 | Forced in 2002 | Forced in 2002 |
| 11N | WB Low | Forced Out | High | Middle | Yes | Yes | Yes | Low | 32,398 | 46,749 | Forced Out | Forced Out |
| 12 | WB Middle | High | Middle | Low | Yes | Yes | Yes | Low | 35,653 | 52,230 | 2004 | Not Installed |
| 12F | WB Middle | High | Middle | Low | Yes | Yes | Yes | Low | 35,686 | 52,273 | Forced in 2002 | Forced in 2002 |
| 12N | WB Middle | Forced Out | Middle | Low | Yes | Yes | Yes | Low | 35,670 | 52,266 | Forced Out | Forced Out |
| 13 | WB Middle | High | Low | Low | Yes | Yes | Yes | Low | 35,438 | 51,817 | 2006 | Not Installed |
| 14F | WB Middle | High | Low | Low | Yes | Yes | Yes | Low | 35,497 | 51,887 | Forced in 2002 | Forced in 2002 |
| 14N | WB Middle | Forced Out | Low | Low | Yes | Yes | Yes | Low | 35,450 | 51,848 | Forced Out | Forced Out |
| 15 | EBRD | High | Low | Low | Yes | Yes | Yes | Low | 29,129 | 42,787 | 2010 | Not Installed |
| 15F | EBRD | High | Low | Low | Yes | Yes | Yes | Low | 29,293 | 42,956 | Forced in 2002 | Forced in 2002 |
| 15N | EBRD | Forced Out | Low | Low | Yes | Yes | Yes | Low | 29,136 | 42,859 | Forced Out | Forced Out |
| 16 | EBRD | Middle | Middle | Middle | Yes | Yes | Yes | Low | 30,434 | 44,746 | 2002 | 2003 |
| 16F | EBRD | Middle | Middle | Middle | Yes | Yes | Yes | Low | 30,434 | 44,747 | Forced in 2002 | Forced in 2002 |
| 16N | EBRD | Forced Out | Middle | Middle | Yes | Yes | Yes | Low | Same as Case 18N | | Forced Out | Forced Out |
| 17 (Not Used) | | | | | | | | | | | | |
| 18 | EBRD | High | Middle | Middle | Yes | Yes | Yes | Low | 30,535 | 44,954 | 2006 | 2010 |
| 18F | EBRD | High | Middle | Middle | Yes | Yes | Yes | Low | 30,590 | 45,010 | Forced in 2002 | Forced in 2002 |
| 18N | EBRD | Forced Out | Middle | Middle | Yes | Yes | Yes | Low | 30,558 | 45,112 | Forced Out | Forced Out |
| 19 (Not Used) | | | | | | | | | | | | |
| 20 | WB Low | Middle | Not Available | Middle | Yes | Yes | Yes | Low | 32,440 | 47,120 | 2002 | 2002 |
| 20N | WB Low | Forced Out | Not Available | Middle | Yes | Yes | Yes | Low | 32,784 | 47,795 | Forced Out | Forced Out |

| | | | | | | | | | | | | |
|-----|--------------|------------|----------------------------|--------|-----|-----|-----|-----|--------|--------|-------------------|-------------------|
| 20H | WB Low | High | Available Not Available | Middle | Yes | Yes | Yes | Low | 32,547 | 47,265 | 2003 | 2005 |
| 20L | WB Low | Low | Available Not Available | Middle | Yes | Yes | Yes | Low | 32,318 | 46,865 | 2002 | 2002 |
| 21 | WB Middle | Middle | Available Not Available | Middle | Yes | Yes | Yes | Low | 38,260 | 56,761 | 2002 | 2002 |
| 21N | WB Middle | Forced Out | Available Not Available | Middle | Yes | Yes | Yes | Low | 38,833 | 57,714 | Forced Out | Forced Out |
| 21H | WB Middle | High | Available Not Available | Middle | Yes | Yes | Yes | Low | 38,415 | 57,024 | 2002 | 2002 |
| 21L | WB Middle | Low | Available Not Available | Middle | Yes | Yes | Yes | Low | 38,168 | 56,605 | 2002 | 2002 |
| 22 | EBRD | Middle | Available Not Available | Middle | Yes | Yes | Yes | Low | 30,716 | 45,814 | 2002 | 2003 |
| 22N | EBRD | Forced Out | Available Not Available | Middle | Yes | Yes | Yes | Low | 31,029 | 46,517 | Forced Out | Forced Out |
| 22H | EBRD | High | Available Not Available | Middle | Yes | Yes | Yes | Low | 30,835 | 46,040 | 2004 | 2005 |
| 22L | EBRD | Low | Available Not Available | Middle | Yes | Yes | Yes | Low | 30,626 | 45,660 | 2002 | 2002 |
| 23 | WB Low | Forced Out | Available Not Available | Middle | No | No | Yes | Low | 32,794 | 47,801 | Forced Out | Forced Out |
| 24 | WB Middle | Forced Out | Available Not Available | Middle | No | No | Yes | Low | 38,858 | 57,782 | Forced Out | Forced Out |
| 25 | EBRD | Forced Out | Available Not Available | Middle | No | No | Yes | Low | 31,038 | 46,553 | Forced Out | Forced Out |
| 26 | WB Low | Low | Middle | Middle | Yes | Yes | Yes | Low | 32,024 | 45,862 | 2002 | 2002 |
| 27 | WB Low | Low | Middle | Low | Yes | Yes | Yes | Low | 30,598 | 43,893 | 2002 | 2003 |
| 28 | WB Low | Low | Low | Middle | Yes | Yes | Yes | Low | 31,875 | 45,515 | 2002 | 2002 |
| 29 | WB Low | Low | Low | Low | Yes | Yes | Yes | Low | 30,529 | 43,650 | 2002 | 2003 |
| 30 | WB Low | Low | High | Middle | Yes | Yes | Yes | Low | 32,117 | 46,179 | 2002 | 2002 |
| 31 | WB Low | Low | High | Low | Yes | Yes | Yes | Low | 30,626 | 43,999 | 2002 | 2003 |
| 32 | WB Low | Middle | High | Low | Yes | Yes | Yes | Low | 30,700 | 44,137 | 2003 | 2005 |
| 32F | WB Low | Middle | High | Low | Yes | Yes | Yes | Low | 30,721 | 44,158 | Forced in 2002 | Forced in 2002 |
| 32N | WB Low | Forced Out | High | Low | Yes | Yes | Yes | Low | 30,794 | 44,349 | Forced Out | Forced Out |
| 33 | WB Low | High | Middle | Low | Yes | Yes | Yes | Low | 30,741 | 44,191 | 2008 | Not Installed |
| 33F | WB Low | High | Middle | Low | Yes | Yes | Yes | Low | 30,848 | 44,312 | Forced in 2002 | Forced in 2002 |
| 34 | WB Low | High | Low | Middle | Yes | Yes | Yes | Low | 32,044 | 45,855 | 2008 | Not Installed |

| | | | | | | | | | | | | |
|-----|-----------|------------|--------|--------|-----|-----|-----|-----|--------|--------|----------------|----------------|
| 34F | WB Low | High | Low | Middle | Yes | Yes | Yes | Low | 32,122 | 45,933 | Forced in 2002 | Forced in 2002 |
| 35 | WB Low | High | High | Low | Yes | Yes | Yes | Low | 30,803 | 44,430 | 2005 | 2007 |
| 35F | WB Low | High | High | Low | Yes | Yes | Yes | Low | 30,893 | 44,521 | Forced in 2002 | Forced in 2002 |
| 36 | WB Middle | High | High | High | Yes | Yes | Yes | Low | 37,837 | 55,900 | 2002 | 2003 |
| 37 | WB Middle | Low | Low | Low | Yes | Yes | Yes | Low | 35,251 | 51,469 | 2002 | 2002 |
| 38 | WB Low | High | Low | High | Yes | Yes | Yes | Low | 32,134 | 46,101 | 2007 | 2010 |
| 38F | WB Low | High | Low | High | Yes | Yes | Yes | Low | 32,206 | 46,173 | Forced in 2002 | Forced in 2002 |
| 39 | EBRD | Low | Low | Low | Yes | Yes | Yes | Low | 29,037 | 42,528 | 2003 | 2004 |
| 39F | EBRD | Low | Low | Low | Yes | Yes | Yes | Low | 29,047 | 42,538 | Forced in 2002 | Forced in 2002 |
| 40 | WB Middle | High | Middle | Middle | Yes | Yes | Yes | Low | 37,444 | 54,980 | 2002 | 2006 |
| 40F | WB Middle | High | Middle | Middle | Yes | Yes | Yes | Low | 37,456 | 54,992 | Forced in 2002 | Forced in 2002 |
| 41 | WB Middle | Middle | Middle | Low | Yes | Yes | Yes | Low | 35,532 | 52,012 | 2002 | 2002 |
| 42 | WB Middle | Low | Middle | Middle | Yes | Yes | Yes | Low | 37,208 | 54,572 | 2002 | 2002 |
| 43 | WB Middle | Low | Middle | Low | Yes | Yes | Yes | Low | 35,440 | 51,856 | 2002 | 2002 |
| 44 | EBRD | High | Middle | Low | Yes | Yes | Yes | Low | 29,223 | 43,067 | 2008 | Not Installed |
| 44F | EBRD | High | Middle | Low | Yes | Yes | Yes | Low | 29,360 | 43,216 | Forced in 2002 | Forced in 2002 |
| 44N | EBRD | Forced Out | Middle | Low | Yes | Yes | Yes | Low | 29,228 | 43,087 | Forced Out | Forced Out |
| 45 | EBRD | Middle | Middle | Low | Yes | Yes | Yes | Low | 29,164 | 42,913 | 2004 | 2005 |
| 45F | EBRD | Middle | Middle | Low | Yes | Yes | Yes | Low | 29,205 | 42,954 | Forced in 2002 | Forced in 2002 |
| 45N | EBRD | Forced Out | Middle | Low | Yes | Yes | Yes | Low | 29,228 | 43,087 | Forced Out | Forced Out |
| 46 | EBRD | Low | Middle | Middle | Yes | Yes | Yes | Low | 30,343 | 44,591 | 2002 | 2002 |
| 47 | EBRD | Low | Middle | Low | Yes | Yes | Yes | Low | 29,103 | 42,788 | 2003 | 2004 |
| 47F | EBRD | Low | Middle | Low | Yes | Yes | Yes | Low | 29,113 | 42,798 | Forced in 2002 | Forced in 2002 |
| 48 | WB Low | High | High | High | Yes | Yes | Yes | Low | 32,438 | 46,835 | 2002 | 2006 |
| 48F | WB Low | High | High | High | Yes | Yes | Yes | Low | 32,457 | 46,854 | Forced in 2002 | Forced in 2002 |
| 49 | WB Low | High | Middle | High | Yes | Yes | Yes | Low | 32,323 | 46,488 | 2005 | 2010 |

| | | | | | | | | | | | | |
|-----|-----------|-------------|--------|---------------|-----|-----|-----|-----|--------|--------|----------------|----------------|
| 49F | WB Low | High | Middle | High | Yes | Yes | Yes | Low | 32,360 | 46,525 | Forced in 2002 | Forced in 2002 |
| 49N | WB Low | Forced Out | Middle | High | Yes | Yes | Yes | Low | 32,349 | 46,652 | Forced Out | Forced Out |
| 50 | WB Middle | High | Middle | High | Yes | Yes | Yes | Low | 37,551 | 55,257 | 2002 | 2006 |
| 50F | WB Middle | High | Middle | High | Yes | Yes | Yes | Low | 37,560 | 55,266 | Forced in 2002 | Forced in 2002 |
| 50N | WB Middle | Forced Out | Middle | High | Yes | Yes | Yes | Low | 37,647 | 55,505 | Forced Out | Forced Out |
| 51 | WB Middle | Middle | Middle | High | Yes | Yes | Yes | Low | 37,406 | 55,004 | 2002 | 2002 |
| 52 | WB Middle | Low | Middle | High | Yes | Yes | Yes | Low | 37,313 | 54,848 | 2002 | 2002 |
| 53 | WB Low | Middle | Middle | High | Yes | Yes | Yes | Low | 32,205 | 46,263 | 2002 | 2002 |
| 54 | WB Low | Low | Middle | High | Yes | Yes | Yes | Low | 32,113 | 46,106 | 2002 | 2002 |
| 55 | EBRD | High | Middle | High | Yes | Yes | Yes | Low | 30,623 | 45,211 | 2006 | 2010 |
| 55F | EBRD | High | Middle | High | Yes | Yes | Yes | Low | 30,673 | 45,260 | Forced in 2002 | Forced in 2002 |
| 55N | EBRD | Forced Out | Middle | High | Yes | Yes | Yes | Low | 30,648 | 45,380 | Forced Out | Forced Out |
| 56 | EBRD | Middle | Middle | High | Yes | Yes | Yes | Low | 30,517 | 44,997 | 2002 | 2003 |
| 56F | EBRD | Middle | Middle | High | Yes | Yes | Yes | Low | 30,518 | 44,998 | Forced in 2002 | Forced in 2002 |
| 56N | EBRD | Forced Out | Middle | High | Yes | Yes | Yes | Low | 30,648 | 45,380 | Forced Out | Forced Out |
| 57 | EBRD | Low | Middle | High | Yes | Yes | Yes | Low | 30,426 | 44,843 | 2002 | 2002 |
| 58 | WB Low | Middle | Middle | Gas - 1.80/GJ | Yes | Yes | Yes | Low | 30,498 | 43,787 | 2003 | 2005 |
| 59 | WB Low | Middle | Middle | Gas- 2.00/GJ | Yes | Yes | Yes | Low | 30,961 | 44,489 | 2002 | 2004 |
| 60 | Flat | Middle | Middle | Middle | Yes | Yes | Yes | Low | 26,430 | 34,987 | 2002 | Not Installed |
| 60F | Flat | Middle | Middle | Middle | Yes | Yes | Yes | Low | 26,462 | 35,040 | Forced in 2002 | Forced in 2002 |
| 60N | Flat | Forced Out | Middle | Middle | Yes | Yes | Yes | Low | 26,448 | 35,020 | Forced Out | Forced Out |
| 61 | WB Low | 622.1/740 | Middle | Middle | Yes | Yes | Yes | Low | 32,132 | 46,044 | 2002 | 2002 |
| 61A | WB Low | 622.1/745 | Middle | Middle | Yes | Yes | Yes | Low | 32,134 | 46,048 | 2002 | 2003 |
| 61B | WB Low | 740/740 | Middle | Middle | Yes | Yes | Yes | Low | 32,181 | 46,128 | 2002 | 2002 |
| 62 | WB Low | 747.3/702.5 | Middle | Middle | Yes | Yes | Yes | Low | 32,168 | 46,106 | 2003 | 2002 |

| | | | | | | | | | | | | |
|--|-----------|-------------|--------|--------|-----|-----|-----|---------------|--------|--------|----------------|-----------------|
| 63 | WB Low | Middle | Middle | Middle | Yes | Yes | Yes | Not Available | 32,174 | 46,329 | 2002 | 2007 |
| (Nuclear units kept at 67% Capacity Factor, including K2/R4) | | | | | | | | | | | | |
| 64 | WB Low | Middle | Middle | Middle | Yes | Yes | Yes | Low | 24,987 | 29,846 | 2006 | 2007 |
| (Cost of Capital = 16 %real) | | | | | | | | | | | | |
| 65 | WB Low | Middle | Middle | Middle | Yes | Yes | Yes | Low | 21,628 | 24,228 | 2007 | 2009 |
| (Cost of Capital = 20% real) | | | | | | | | | | | | |
| 66 | WB Low | Middle | Middle | Middle | Yes | Yes | Yes | Low | 28,189 | 36,242 | 2003 | 2005 |
| 66F | WB Low | Middle | Middle | Middle | Yes | Yes | Yes | Low | 28,206 | 36,259 | Forced in 2002 | Forced in 2002 |
| 67 | WB Low | Middle | Middle | Middle | Yes | Yes | Yes | Low | 32,106 | 45,991 | 2002 | 2002 |
| (No restriction on number of low level rehab units) | | | | | | | | | | | | |
| 68F | WB Low | Middle | Middle | Middle | Yes | Yes | Yes | Low | 32,225 | 46,156 | Forced in 2002 | Forced in 2002 |
| (One year delay in operation after completion expected in optimum time) | | | | | | | | | | | | |
| 69 | WB Low | Middle | Middle | Middle | Yes | Yes | Yes | Low | 32,162 | 46,138 | 2002 | Forced Out |
| (Only K2 available, no R4) | | | | | | | | | | | | |
| 70 | Extr.Drop | Middle | Middle | Middle | Yes | Yes | Yes | Low | 28,282 | 40,774 | 2002 | 2005 |
| 70F | Extr.Drop | Middle | Middle | Middle | Yes | Yes | Yes | Low | 28,256 | 40,788 | Forced in 2002 | Forced in 2002 |
| (Annual Energy drops to 145,000 GWh in 2001, grows at 4% thereafter) | | | | | | | | | | | | |
| 71 | WB Low | 747.3/702.5 | Middle | Middle | Yes | Yes | Yes | Low | 32,181 | 46,118 | 2002 | 2005(earliest) |
| (Deliberate separate completion, K2 separate middle completion cost, R4 separate middle completion, earliest installation date 2005) | | | | | | | | | | | | |
| 72 | WB Low | 747.3/899.2 | Middle | Middle | Yes | Yes | Yes | Low | 32,213 | 46,207 | 2002 | 2010 |
| (Deliberate separate completion, K2 separate middle completion cost, R4 separate high completion, earliest installation date 2005) | | | | | | | | | | | | |
| 73 | WB Low | Middle | High | High | Yes | Yes | Yes | Low | 32,303 | 46,592 | 2002 | 2002 |
| 75 | WB Low | Low | High | High | Yes | Yes | Yes | Low | 32,211 | 46,436 | 2002 | 2002 |
| 74 | WB Low | Middle | Low | High | Yes | Yes | Yes | Low | 32,252 | 45,911 | 2002 | 2002 |
| 76 | WB Low | Low | Low | High | Yes | Yes | Yes | Low | 31,960 | 45,755 | 2002 | 2002 |
| 77 | EBRD | High | High | High | Yes | Yes | Yes | Low | 30,726 | 45,551 | 2004 | 2006 |

| | | | | | | | | | | | | |
|-----|--------------|--------|------|--------|-----|-----|-----|-----|--------|--------|-----------|---------------|
| 78 | EBRD | High | High | Middle | Yes | Yes | Yes | Low | 30,637 | 45,294 | 2004 | 2006 |
| 79 | EBRD | High | High | Low | Yes | Yes | Yes | Low | 29,260 | 43,188 | 2006 | Not Installed |
| 80 | EBRD | High | Low | High | Yes | Yes | Yes | Low | 30,459 | 44,849 | 2008 | 2010 |
| 81 | EBRD | High | Low | Middle | Yes | Yes | Yes | Low | 30,373 | 44,595 | 2008 | 2010 |
| 82 | EBRD | Middle | High | High | Yes | Yes | Yes | Low | 30,607 | 45,325 | 2002 | 2003 |
| 83 | EBRD | Middle | High | Middle | Yes | Yes | Yes | Low | 30,522 | 45,071 | 2002 | 2003 |
| 84 | EBRD | Middle | High | Low | Yes | Yes | Yes | Low | 29,192 | 43,023 | 2004 | 2005 |
| 85 | EBRD | Middle | Low | High | Yes | Yes | Yes | Low | 30,385 | 44,668 | 2002 | 2005 |
| 86 | EBRD | Middle | Low | Middle | Yes | Yes | Yes | Low | 30,307 | 44,421 | 2002 | 2005 |
| 87 | EBRD | Middle | Low | Low | Yes | Yes | Yes | Low | 29,095 | 42,650 | 2004 | 2007 |
| 88 | EBRD | Low | High | High | Yes | Yes | Yes | Low | 30,516 | 45,170 | 2002 | 2002 |
| 89 | EBRD | Low | High | Middle | Yes | Yes | Yes | Low | 30,432 | 44,917 | 2002 | 2002 |
| 90 | EBRD | Low | High | Low | Yes | Yes | Yes | Low | 29,131 | 42,898 | 2003 | 2004 |
| 91 | EBRD | Low | Low | High | Yes | Yes | Yes | Low | 30,298 | 44,516 | 2002 | 2002 |
| 92 | EBRD | Low | Low | Middle | Yes | Yes | Yes | Low | 30,220 | 44,271 | 2002 | 2002 |
| 93 | WB | High | High | Middle | Yes | Yes | Yes | Low | 37,728 | 55,598 | 2002 | 2003 |
| 94 | Middle WB | High | High | Low | Yes | Yes | Yes | Low | 35,752 | 52,425 | 2002 | Not Installed |
| 94F | Middle WB | High | High | Low | Yes | Yes | Yes | Low | 35,773 | 52,455 | Forced In | |
| 95 | Middle WB | High | Low | High | Yes | Yes | Yes | Low | 37,270 | 54,668 | 2002 | 2006 |
| 96 | Middle WB | High | Low | Middle | Yes | Yes | Yes | Low | 37,166 | 54,402 | 2002 | 2006 |
| 97 | Middle WB | Middle | High | High | Yes | Yes | Yes | Low | 37,682 | 55,639 | 2002 | 2002 |
| 98 | Middle WB | Middle | High | Middle | Yes | Yes | Yes | Low | 37,574 | 55,338 | 2002 | 2002 |
| 99 | Middle WB | Middle | High | Low | Yes | Yes | Yes | Low | 35,619 | 52,193 | 2002 | 2002 |
| 100 | Middle WB | Middle | Low | High | Yes | Yes | Yes | Low | 37,130 | 54,421 | 2002 | 2002 |
| 101 | Middle WB | Middle | Low | Middle | Yes | Yes | Yes | Low | 37,028 | 54,157 | 2002 | 2002 |
| 102 | Middle WB | Middle | Low | Low | Yes | Yes | Yes | Low | 35,343 | 51,625 | 2002 | 2003 |
| 103 | Middle WB | Low | High | High | Yes | Yes | Yes | Low | 37,590 | 55,483 | 2002 | 2002 |
| 104 | Middle WB | Low | High | Middle | Yes | Yes | Yes | Low | 37,482 | 55,181 | 2002 | 2002 |

| | | | | | | | | | | | | |
|-----|--------------|-----|------|--------|-----|-----|-----|-----|--------|--------|------|------|
| 105 | WB Middle | Low | High | Low | Yes | Yes | Yes | Low | 35,527 | 52,037 | 2002 | 2002 |
| 106 | WB Middle | Low | Low | High | Yes | Yes | Yes | Low | 37,058 | 54,265 | 2002 | 2002 |
| 107 | WB Middle | Low | Low | Middle | Yes | Yes | Yes | Low | 36,935 | 54,000 | 2002 | 2002 |

APPENDIX C
Decision Trees

**Khmelnitsky 2 and Rovno 4 Completion Due Diligence
Least Cost Planning Analysis
Joint K2/R4 Completion Program
Probability of Total System Present Value Cost and Optimal K2/R4 Installation Year**

| Load Forecast | K2/R4 Completion Cost | Fossil Rehab Cost | Fuel Cost | Prob-ability of Outcome | Total PV System Cost | Optimal Service Year | |
|---------------|-----------------------|-------------------|---------------|-------------------------|----------------------|----------------------|---------------|
| | | | | | | K2 | R4 |
| Middle 50% | High 26% | High 25% | High 25% | 0.813% | 46,835 | 2002 | 2006 |
| | | | Middle 50% | 1.625% | 46,579 | 2003 | 2007 |
| | | | Low 25% | 0.813% | 44,430 | 2005 | 2007 |
| | | Middle 50% | High 25% | 1.625% | 46,488 | 2005 | 2010 |
| | | | Middle 50% | 3.250% | 46,239 | 2006 | 2010 |
| | | | Low 25% | 1.625% | 44,191 | 2008 | Not Installed |
| | | Low 25% | High 25% | 0.813% | 46,101 | 2007 | 2010 |
| | | | Middle 50% | 1.625% | 45,855 | 2008 | Not Installed |
| | | | Low 25% | 0.813% | 43,890 | 2010 | Not Installed |
| | Middle 40% | High 25% | High 25% | 1.250% | 46,592 | 2002 | 2002 |
| | | | Middle 50% | 2.500% | 46,335 | 2002 | 2002 |
| | | | Low 25% | 1.250% | 44,137 | 2003 | 2005 |
| | | Middle 50% | High 25% | 2.500% | 46,263 | 2002 | 2002 |
| | | | Middle 50% | 5.000% | 46,018 | 2002 | 2002 |
| | | | Low 25% | 2.500% | 44,028 | 2003 | 2005 |
| | | Low 25% | High 25% | 1.250% | 45,911 | 2002 | 2002 |
| | | | Middle 50% | 2.500% | 45,670 | 2002 | 2003 |
| | | | Low 25% | 1.250% | 43,784 | 2003 | 2007 |
| Low 34% | High 25% | High 25% | 1.063% | 46,436 | 2002 | 2002 | |
| | | Middle 50% | 2.125% | 46,179 | 2002 | 2002 | |
| | | Low 25% | 1.063% | 43,999 | 2002 | 2003 | |
| | Middle 50% | High 25% | 2.125% | 46,106 | 2002 | 2002 | |
| | | Middle 50% | 4.250% | 45,862 | 2002 | 2002 | |
| | | Low | 2.125% | 43,893 | 2002 | 2003 | |

**Khmelnitsky 2 and Rovno 4 Completion Due Diligence
Least Cost Planning Analysis
Joint K2/R4 Completion Program
Probability of Total System Present Value Cost and Optimal K2/R4 Installation Year**

| Load Forecast | K2/R4 Completion Cost | Fossil Rehab Cost | Fuel Cost | Probability of Outcome | Total PV System Cost | Optimal Service Year | | |
|---------------|-----------------------|-------------------|---------------|------------------------|----------------------|----------------------|---------------|------|
| | | | | | | K2 | R4 | |
| High 25% | High 26% | High 25% | High 25% | 0.406% | 55,900 | 2002 | 2003 | |
| | | | Middle 50% | 0.813% | 55,598 | 2002 | 2003 | |
| | | | Low 25% | 0.406% | 52,425 | 2002 | Not Installed | |
| | | Middle 50% | High 25% | 0.813% | 55,257 | 2002 | 2006 | |
| | | | Middle 50% | 1.625% | 54,980 | 2002 | 2006 | |
| | | | Low 25% | 0.813% | 52,230 | 2004 | Not Installed | |
| | | Low 25% | High 25% | 0.406% | 54,668 | 2002 | 2006 | |
| | | | Middle 50% | 0.813% | 54,402 | 2002 | 2006 | |
| | | | Low 25% | 0.406% | 51,817 | 2006 | Not Installed | |
| | Middle 40% | High 25% | High 25% | High 25% | 0.625% | 55,639 | 2002 | 2002 |
| | | | | Middle 50% | 1.250% | 55,338 | 2002 | 2002 |
| | | | | Low 25% | 0.625% | 52,193 | 2002 | 2002 |
| | | Middle 50% | High 25% | 1.250% | 55,004 | 2002 | 2002 | |
| | | | Middle 50% | 2.500% | 54,728 | 2002 | 2002 | |
| | | | Low 25% | 1.250% | 52,012 | 2002 | 2002 | |
| | | Low 25% | High 25% | 0.625% | 54,421 | 2002 | 2002 | |
| | | | Middle 50% | 1.250% | 54,157 | 2002 | 2002 | |
| | | | Low 25% | 0.625% | 51,625 | 2002 | 2003 | |
| | Low 34% | High 25% | High 25% | High 25% | 0.531% | 55,483 | 2002 | 2002 |
| | | | | Middle 50% | 1.063% | 55,181 | 2002 | 2002 |
| | | | | Low 25% | 0.531% | 52,037 | 2002 | 2002 |
| Middle 50% | | High 25% | 1.063% | 54,848 | 2002 | 2002 | | |
| | | Middle 50% | 2.125% | 54,709 | 2002 | 2002 | | |
| | | Low 25% | 1.063% | 51,856 | 2002 | 2002 | | |

**Khmelnitsky 2 and Rovno 4 Completion Due Diligence
Least Cost Planning Analysis
Joint K2/R4 Completion Program
Probability of Total System Present Value Cost and Optimal K2/R4 Installation Year**

| Load Forecast | K2/R4 Completion Cost | Fossil Rehab Cost | Fuel Cost | Probability of Outcome | Total PV System Cost | Optimal Service Year | | |
|---------------|-----------------------|-------------------|------------|------------------------|----------------------|----------------------|---------------|------|
| | | | | | | K2 | R4 | |
| Low 25% | High 26% | High 25% | High 25% | 0.406% | 45,551 | 2004 | 2006 | |
| | | | Middle 50% | 0.813% | 45,294 | 2004 | 2006 | |
| | | | Low 25% | 0.406% | 43,188 | 2006 | Not Installed | |
| | | Middle 50% | High 25% | 0.813% | 45,211 | 2006 | 2010 | |
| | | | Middle 50% | 1.625% | 44,954 | 2006 | 2010 | |
| | | | Low 25% | 0.813% | 43,067 | 2008 | Not Installed | |
| | | Low 25% | High 25% | 0.406% | 44,849 | 2008 | 2010 | |
| | | | Middle 50% | 0.813% | 44,595 | 2008 | 2010 | |
| | | | Low 25% | 0.406% | 42,787 | 2010 | Not Installed | |
| | | Middle 40% | High 25% | High 25% | 0.625% | 45,325 | 2002 | 2003 |
| | | | | Middle 50% | 1.250% | 45,071 | 2002 | 2003 |
| | | | | Low 25% | 0.625% | 43,023 | 2004 | 2005 |
| | High 25% | | | 1.250% | 44,997 | 2002 | 2003 | |
| | Middle 50% | | Middle 50% | 2.500% | 44,746 | 2002 | 2003 | |
| | | | Low 25% | 1.250% | 42,913 | 2004 | 2005 | |
| | | | High 25% | 0.625% | 44,668 | 2002 | 2005 | |
| | | | Middle 50% | 1.250% | 44,421 | 2002 | 2005 | |
| | Low 25% | | Low 25% | 0.625% | 42,650 | 2004 | 2007 | |
| | | | High 25% | 0.531% | 45,170 | 2002 | 2002 | |
| | | | Middle 50% | 1.063% | 44,917 | 2002 | 2002 | |
| | | | Low 25% | 0.531% | 42,898 | 2003 | 2004 | |
| | Low 34% | Middle 50% | High 25% | 1.063% | 44,843 | 2002 | 2002 | |
| | | | Middle 50% | 2.125% | 44,591 | 2002 | 2002 | |
| | | | Low 25% | 1.063% | 42,788 | 2003 | 2004 | |
| Low 25% | | High 25% | 0.531% | 44,516 | 2002 | 2002 | | |
| | | Middle 50% | 1.063% | 44,271 | 2002 | 2002 | | |

APPENDIX D

Comparison of Surrey Panel Report and Stone & Webster Report

**Comparison
of
Surrey Panel Report
to
Most recent Stone & Webster Study**

The first portion of this comparison is a response to general issues raised by the Surrey Panel concerning the reliability or usefulness of their study's information. The comments seek to show how reliability, thoroughness and robustness of the data has been improved in the past year. The latter portion of this comparison lays out the comparison of data and seeks to demonstrate why a completion or no-completion decision is supported by each study's data.

Comments to Statements made in Surrey Report

(Excerpts from Surrey Panel report are shown in *italics*.)

Executive Summary -

- *Before a decision could be taken with confidence....Much more would need to be known about five factors.*
 - (i) *The future trends of electricity and energy demand.....*

In setting up the analysis, care was taken to use a broad range of possible outcomes in the use of electricity. This included a significant change in the use of electricity that reflects the requirement to pay for what is used. The load factor of the system was dropped from the Soviet-era level of 73% to 65%, which is a more normally expected value by Western standards for a mix of industrial commercial and residential consumption. It should be noted that this is shown on a gross generation basis, which includes generating station auxiliary power use and transmission losses, and as such will be slightly higher than a net delivered power load factor. Also, a DSM program parallel to that used in the Surrey Panel study was included in the latest study.

(ii) *Whether and when the nuclear safety upgrade programme will be carried out and whether it will significantly increase the output of the existing nuclear reactors.*

The continued attention to the performance of the existing nuclear units has brought new evidence to light that there are both solutions and economic value to applying those solutions. A distinction has been made now between safety upgrades, which produce no performance or availability improvement, and those factors, such as outage management, materials management, and controls improvements, which will improve output. The cost and value of improved performance is shown in the most recent Stone & Webster Study.

(iii) *The effects of the thermal plant rehabilitation programme and the plan to rationalize the coal industry, raise productivity and put the industry on a commercial basis.*

The effects of the early stages of the thermal rehabilitation program will not be known for several years, nor is it likely that the coal industry will rapidly turn around,

given the current state of the mines and coal cleaning system. By that time most of the existing fossil-fired generation fleet will have failed or be quite unreliable. Thus, a wait-and-see approach may cause serious problems with reliability of supply. For example, if the Ukrainian economy were to recover at a rate that matched the World Bank middle load forecast, the generating system as now configured would provide below-standard reliability starting in 2003. For the lower load forecasts this would begin in 2007 or 2008. Because of the large size of the Ukrainian system, the amount of rehabilitation work required is in the order of several \$Billion. To keep reliability standards by these dates action should not be postponed and then a “crash program” instituted, since this will inherently drive up costs and cause disruption of the system because so many units were unavailable as they undergo rehabilitation. This latter problem is exacerbated if K2 and R4 are not completed.

The rather pessimistic depiction of the Ukrainian coal industry given by Mr. Parker in his Supporting Paper to the Surrey Panel report appears to be seconded by ensuing conditions. The past year has not shown any improvement in coal industry performance. Continued research by international as well as Ukrainian coal experts in fact appears to show even more difficult times ahead. There was little evidence in the data gathering process conducted in Kiev in December, 1997, that restructuring of the coal industry was in process, or even likely in the near term. One major problem which was raised at that time and which cannot be “restructured” is that the coal seams in Ukraine are getting thin and deep underground. If possible, whole new mines using fresh seams will likely have to be built in order to meet the needs of the power generation industry in a restored Ukrainian economy that increases its reliance on indigenous coal.

(iv) The cost of completing K2/R4, including upgrading them where possible to current Western safety standards and of operating them (including the fuel cycle and non-fuel operations and maintenance, waste disposal and decommissioning.

Since the date of the Surrey Report considerable progress has been made in improving the cost estimates for both completion and operating costs. Decommissioning, waste disposal, fuel and non-fuel operating cost estimates have been scrutinized and included in the overall costs used to represent K2 and R4.

(v) When will the great bulk of electricity bills be paid and the cash crisis of the electricity supply industry be over?

This issue still remains and needs to be resolved. The Ukrainian government has made this a priority issue, we believe, but the results must be seen.

- *We have used a least cost planning (LCP) model as a supporting tool. However, we were cautious about relying heavily on this methodology for the following reasons:*

(i) The model results derive from the assumptions used. If these are not fully transparent, it is impossible to know which factors are most important in determining the outcome.

The concept of transparency is important in the analysis. We have seen that the model used can produce either the Surrey Panel’s results or the results shown in the most recent study, both outcomes being dependent on the data used, not the

model.

- (iii) *The LCP methodology was developed for and used by vertically integrated electric utilities...The more competitive power generation becomes in Ukraine, the less relevant LCP methodology will be for the development of this sector (as in England and Wales).*

It is important to make the distinction between the model used, EGEAS, and the LCP methodology. For over a year Stone & Webster has been using the EGEAS model for extensive work in modeling competitive power markets, both in the U.S. and in several other countries. Changes introduced to the model allow bid-based pool modeling and analysis of operating income by unit. This has been used to determine profitability for plants, forward market clearing price, stranded cost effects, and asset valuation.

The question raised by the Surrey Panel about the effects of competition should be addressed more thoroughly than it has so far in any study, more from the point of view that the completion and operation of K2 and R4 will be profitable in the pool. Since they will not set the market clearing price, K2 and R4 will be paid at a rate set by other bidders. Will that be enough to cover their completion and operating costs?

Comparison of Data

There appears to be five areas in which the data used by the Surrey Panel and the most recent analysis differ. All five of these shifts tend to move the cost of construction and operation of the Ukrainian system more toward the conclusion that the completion of K2 and R4 is the economic choice. The five areas are: load forecast, fossil unit availability, fossil fuel cost, nuclear unit availability, and nuclear operations and maintenance costs.

Load Forecast

The estimated annual energy production and gross peak load at selected years for the two studies are shown in the following table.

Electricity Production Forecasts

| | 2000 | | 2010 | |
|----------------------|-----------|--------------|-----------|--------|
| | Peak (GW) | Energy (TWh) | Peak (GW) | Energy |
| <u>(TWh)</u> | | | | |
| <u>Surrey Panel</u> | | | | |
| Low | 30.8 | 189 | 34.7 | 213 |
| Middle | 30.8 | 189 | 37.5 | 230 |
| High | 30.8 | 189 | 41.4 | 254 |
| <u>Current Study</u> | | | | |
| Low (EBRD) | 24.8 | 154.8 | 40.1 | 228.2 |
| Middle (WB Low) | 27.7 | 172.8 | 39.3 | 223.5 |
| High (WB Middle) | 30.7 | 191.2 | 45.8 | 260.9 |

In comparing these two sets of forecasts, one can see that in general the Current Study's estimate of the energy and demand are higher in the later years, even though lower in the early years. Also, in the later years of the analysis, the Current Study assumes a lower capacity factor than the Surrey Panel. For example, the Surrey Panel's middle forecast projection for 2010 has a capacity factor of 70%, while the corresponding forecast used in the Current Study has a capacity factor of 65%. This was done to reflect changes in the electricity consumption patterns when consumers are going to have to pay for what they use.

Fossil and Nuclear Unit Availability and Operating Costs

On the last two pages of this comparison are tabulations of the operating data for fossil-fired power plants and nuclear plants used in the two studies. There are sharp differences in four areas of the data which appear to produce the shift of the economics of the completion/no-completion choice. They are fossil unit availability, fossil unit fuel costs, nuclear unit availability, and nuclear unit O & M costs.

The availability of all fossil-fuel generators is shown in weighted value for both sets of data. The value for the Surrey Panel data is 84% and for the Stone & Webster Study is 62%. Given the state of the Ukrainian generation system, the lower value appears more realistic, even if there were no fuel availability problems. The higher value would be approximately competitive with availability to be expected from a well and continuously maintained fleet of units of the Ukrainian system's service life. There has been no provision for any special overhauls that might restore the existing units to top tier performance, nor do the total non-fuel operation and maintenance costs shown, even if skewed toward the fixed side, provide enough money to repair past degradation of performance. Low level rehabilitation, which would restore the present units to service for up to 15 years at an availability of about 80% , is estimated to cost \$120/kw, or about \$3.38 Billion for the 28,180 MW.

Turning to the cost of fuel and its conversion rate, there is a significant drop in weighted average heat rate, about 10%, from the Surrey Panel report to those used in the Stone & Webster study. However, the cost of the fuel increased from a weighted average of \$1.64/GJ to \$2.28/GJ, or 39%. Most of this increase came from inclusion of the higher cost of the fuel used for co-firing, which was not included in the previous analysis. The cost of coal for existing units was consistent between studies, while gas and mazut were priced higher in the Stone & Webster study.

The higher cost of fuel, even though partially offset by lower heat rates, and the much lower availability levels contribute in combination to much higher operating costs for the fossil fuel units as modeled in the Stone & Webster study. This value difference is captured in a snapshot and simplified way for both sets of data.

The operating data for the nuclear units show essentially the reverse conditions from the fossil units. They have higher availability and lower operation and maintenance costs (at least for K2 and R4) in the Stone & Webster study than in the Surrey Panel report. The missing fixed O & M cost for the existing nuclear units in the Surrey Panel Report is not important in the analysis approach used in both studies.

The higher availability and lower fixed O & M cost for each of the two candidates for completion improve their competitiveness, moving from a cost of \$19.48/MWh to \$14.99/MWh, a reduction of 23%.

The following table shows the average cost of fossil generation (even though incremental or marginal cost would be proper) for 2000 MW at the composite cost rates and availability for the two studies, and compares that to the production costs for K2 and R4 plus charges for completion capital used in the two studies. It is evident from this comparison that the data produces two logically different conclusions.

Total Annual Costs of Power and Capital
2000 MW of Capability

| | <u>Surrey Panel</u> | <u>Stone & Webster</u> |
|---|---------------------|----------------------------|
| Fossil | | |
| Energy Cost Rate | \$25.08/MWh | \$31.30/MWh |
| Nuclear | | |
| Energy Cost Rate | <u>19.48</u> | <u>14.99</u> |
| Difference | 5.60 | 16.31 |
| Total Power cost differential (2000 MW at 75% capacity factor) | \$73.6 million | \$214.3 million |
| Nuclear Capital Carrying Cost | -\$127.3 million | -\$125.2 million |
| Advantage of K2 and R4 Completion | -\$53.7 million | \$89.1 million |

While this table presents the results in a somewhat simplified form, it does show the same switch found in the more complex analyses performed by the computer model.

The Surrey Panel Report states in the Conclusions section of its Executive Summary,

- *Electricity demand has been so reduced by the highly depressed economic situation that there is a large capacity surplus which is likely to last until at least 2010. Installing further surplus generating capacity would use up limited borrowing authority for a purpose not needed and make it more difficult to achieve the efficiency objectives behind the Government's market-based reforms throughout the energy sector.*

This conclusion frames the situation as being only one of installed capacity. The situation facing the Ukrainian system, however, is not one of just raw capacity, but one of economic and reliable energy production. The small example shown in the table above is based on the idea that an investment of capital will produce lower system costs than owning and operating the new facility. In this case the principle is being applied to K2 and R4 completion, but it can be applied to any facility. As such, it is in keeping with the energy efficiency objectives, and in some respects shows the way for market-based reforms that will result in lowering electricity costs to the public.

The latest Stone & Webster study shows that meeting the future needs of the Ukrainian electricity sector will not be an either-or choice on K2 and R4 completion, but a long series of choices of what cost-effective facilities should be streamed into the process. K2 and R4 are part of a larger process, which will include major rehabilitation work on the existing fossil units, refurbishment or replacement of CHP plants, new integration of the Ukrainian system to the rest of the surrounding network, and other choices.

**Generating Plant Performance Comparison
Data as Used in Surrey Panel Report**

| Station | Capacity | | Full Load | Outage Rates | | Availability Net (%) | Fuel Price (\$/GJ) | O & M Costs | | Energy Cost @ |
|------------------|----------|-----------|-----------------------|-----------------------|---------------|-------------------------|-----------------------|---------------------|----------------------|-------------------------------|
| | Rated | Operating | Heat Rate (KJ/kwh) | Sch.Maint. (Weeks) | Forced (%) | | | Fixed (\$/kw-yr) | Variable (\$/MWh) | Max. Availability (\$/MWh) |
| Fossil | | | | | | | | | | |
| Burshtyn | 2280 | 2100 | 10,467 | 4 | 6 | 86% | 1.52 | 36.00 | 2.80 | 23.47 |
| Kurakhov | 1470 | 1330 | 10,844 | 4 | 6 | 86% | 1.52 | 42.00 | 4.10 | 26.14 |
| Ladizhin | 1800 | 1776 | 9,672 | 5 | 8 | 82% | 1.52 | 34.80 | 4.10 | 23.62 |
| Zuev | 1200 | 1160 | 10,020 | 5 | 6 | 84% | 1.52 | 36.00 | 2.80 | 22.90 |
| Krivorozn | 3000 | 2820 | 10,321 | 5 | 7 | 83% | 1.52 | 34.80 | 4.10 | 24.55 |
| Lugansk-8 | 1400 | 1304 | 11,180 | 4 | 6 | 86% | 1.52 | 36.00 | 2.80 | 24.55 |
| Lugansk-2 | 200 | 190 | 12,498 | 3 | 6 | 88% | 1.52 | 48.00 | 4.00 | 29.21 |
| Mironov-1 | 60 | 55 | 16,161 | 4 | 7 | 85% | 1.52 | 48.00 | 4.00 | 34.99 |
| Mironov-2 | 200 | 180 | 14,446 | 4 | 7 | 85% | 1.52 | 48.00 | 4.00 | 32.38 |
| Pridniprovsk-4-1 | 1140 | 1028 | 10,259 | 5 | 7 | 83% | 1.52 | 34.80 | 4.10 | 24.46 |
| Pridniprovsk-4-2 | 600 | 580 | 11,012 | 3 | 6 | 88% | 1.52 | 46.80 | 4.20 | 26.99 |
| Slavyansk-1-1 | 750 | 715 | 10,593 | 6 | 8 | 80% | 1.52 | 32.40 | 3.80 | 24.50 |
| Slavyansk-1-2 | 720 | 670 | 10,091 | 6 | 7 | 81% | 2.05 | 26.40 | 2.60 | 26.99 |
| Slavyansk-2 | 200 | 170 | 12,603 | 3 | 5 | 89% | 2.05 | 58.80 | 2.90 | 36.26 |
| Starobeshevo | 1750 | 1600 | 10,614 | 8.5 | 7 | 77% | 1.52 | 42.00 | 4.10 | 26.49 |
| Tripoli-4 | 1160 | 1120 | 9,881 | 5 | 7 | 83% | 1.52 | 34.80 | 4.10 | 23.88 |
| Tripoli-2 | 600 | 588 | 9,881 | 5 | 6 | 84% | 2.05 | 30.00 | 2.80 | 27.11 |
| Zmieiev-4 | 1100 | 1024 | 10,070 | 5 | 7 | 83% | 1.52 | 34.80 | 4.10 | 24.17 |
| Zmieiev-6 | 1050 | 990 | 10,559 | 4 | 6 | 86% | 1.52 | 42.00 | 4.10 | 25.71 |
| Uglegorsk-4 | 1200 | 1080 | 10,321 | 5 | 6 | 84% | 1.52 | 36.00 | 2.80 | 23.36 |
| Uglegorsk-3 | 2250 | 2025 | 9,672 | 5.5 | 7 | 82% | 2.05 | 26.40 | 2.60 | 26.08 |
| Zaporozhe-4 | 1200 | 1140 | 10,153 | 5 | 6 | 84% | 1.52 | 36.00 | 2.80 | 23.10 |
| Zaporozhe-3 | 2250 | 2190 | 9,253 | 5.5 | 8 | 81% | 2.05 | 26.40 | 2.60 | 25.27 |
| Dobrotvorsk-2 | 300 | 280 | 10,761 | 3 | 5 | 89% | 2.05 | 48.00 | 2.90 | 31.10 |
| Dobrotvorsk-3 | 300 | 270 | 10,300 | 3 | 5 | 89% | 2.05 | 48.00 | 2.90 | 30.16 |
| Composite | 28,180 | 26,385 | 10,285 | | | 84% | 1.64 | | | 25.08 |
| Nuclear | | | | | | | | | | |
| Zaporozhe 1 | 1000 | 950 | 10,552 | 13 | 15 | 60% | 0.79 | 0 | 2.2 | 10.54 |
| Zaporozhe 2 | 1000 | 950 | 10,552 | 13 | 15 | 60% | 0.79 | 0 | 2.2 | 10.54 |
| Zaporozhe 3 | 1000 | 950 | 10,552 | 13 | 15 | 60% | 0.79 | 0 | 2.2 | 10.54 |
| Zaporozhe 4 | 1000 | 950 | 10,552 | 13 | 15 | 60% | 0.79 | 0 | 2.2 | 10.54 |
| Zaporozhe 5 | 1000 | 950 | 10,552 | 13 | 15 | 60% | 0.79 | 0 | 2.2 | 10.54 |
| Zaporozhe 6 | 1000 | 950 | 10,552 | 13 | 15 | 60% | 0.79 | 0 | 2.2 | 10.54 |
| So. Ukraine 1 | 1000 | 935 | 10,552 | 13 | 15 | 60% | 0.59 | 0 | 2.5 | 8.73 |
| So. Ukraine 2 | 1000 | 935 | 10,552 | 13 | 15 | 60% | 0.59 | 0 | 2.5 | 8.73 |
| So. Ukraine 3 | 1000 | 935 | 10,552 | 13 | 15 | 60% | 0.59 | 0 | 2.5 | 8.73 |
| Rovno 1 | 440 | 380 | 10,552 | 8 | 5 | 80% | 0.65 | 0 | 2.6 | 9.46 |
| Rovno 2 | 440 | 380 | 10,552 | 8 | 5 | 80% | 0.65 | 0 | 2.6 | 9.46 |
| Rovno 3 | 1000 | 930 | 10,552 | 13 | 15 | 60% | 0.65 | 0 | 2.6 | 9.46 |
| Khmelnitsky 1 | 1000 | 955 | 10,552 | 13 | 15 | 60% | 0.65 | 0 | 2.6 | 9.46 |
| Khmelnitsky 2 | 1000 | 955 | 10,552 | 13 | 10 | 65% | 0.65 | 40 | 5.6 | 19.48 |
| Rovno 4 | 1000 | 930 | 10,552 | 13 | 10 | 65% | 0.65 | 40 | 5.6 | 19.48 |

Generating Plant Performance Comparison
Data as Used in Stone & Webster Study (After Kiev Data Conference)

| Station | Capacity | | Full Load | Outage Rates | | Availability Net (%) | Fuel Price (\$/GJ) | O & M Costs | | Energy Cost @ |
|-------------------|----------|-----------|-----------------------|-----------------------|---------------|-------------------------|-----------------------|---------------------|----------------------|-------------------------------|
| | Rated | Operating | Heat Rate (KJ/kwh) | Sch.Maint. (Weeks) | Forced (%) | | | Fixed (\$/kw-yr) | Variable (\$/MWh) | Max. Availability (\$/MWh) |
| Fossil | | | | | | | | | | |
| Burshtyn 5-12 | 1520 | 1383 | 9,700 | 9 | 13.5 | 69% | 1.85 | 15.00 | 6.40 | 26.82 |
| Kurakhov | 1470 | 1338 | 9,842 | 9 | 13.5 | 69% | 1.67 | 16.00 | 6.10 | 25.17 |
| Ladizhin | 1800 | 1638 | 9,573 | 9 | 13.5 | 69% | 2.12 | 12.10 | 5.50 | 27.79 |
| Zuev | 1200 | 1092 | 9,240 | 9 | 13.5 | 69% | 1.67 | 12.60 | 5.50 | 23.01 |
| Krivorozn 2-3 | 600 | 564 | 9,738 | 9 | 20.8 | 62% | 1.67 | 12.40 | 5.90 | 24.45 |
| Krivorozn 5-6 | 600 | 564 | 9,738 | 9 | 20.8 | 62% | 1.67 | 12.40 | 5.90 | 24.45 |
| Krivorozn 7-10 | 1200 | 1128 | 9,738 | 9 | 20.8 | 62% | 1.67 | 12.40 | 5.90 | 24.45 |
| Lugansk 12-15 | 800 | 728 | 11,142 | 9 | 13.5 | 69% | 2.12 | 15.90 | 7.00 | 33.24 |
| Pridniprov 11-14 | 1140 | 1037 | 9,940 | 9 | 13.5 | 69% | 1.85 | 15.90 | 6.60 | 27.61 |
| Slavyansk 1 | 720 | 720 | 9,941 | 9 | 20.8 | 62% | 2.65 | 11.70 | 7.50 | 36.00 |
| Staobeshevo 4 | 200 | 210 | 9,875 | 6 | 7.0 | 81% | 0.74 | 17.00 | 7.00 | 16.69 |
| Starobeshevo 5-13 | 1800 | 1593 | 10,400 | 9 | 23.2 | 60% | 1.85 | 15.80 | 7.00 | 29.27 |
| Tripoli 1-4 | 1200 | 1200 | 9,522 | 9 | 20.8 | 62% | 1.85 | 12.30 | 5.50 | 25.38 |
| Tripoli 5-6 | 600 | 561 | 8,870 | 9 | 15.6 | 67% | 2.82 | 14.60 | 7.00 | 34.50 |
| Zmiev 7-10 | 1200 | 1100 | 9,593 | 9 | 14.1 | 69% | 1.85 | 13.40 | 7.50 | 27.47 |
| Zmiev 2,4,6 | 600 | 478 | 10,568 | 9 | 13.4 | 69% | 1.85 | 15.40 | 7.00 | 29.09 |
| Uglegorsk 1-4 | 1200 | 1092 | 9,163 | 9 | 13.5 | 69% | 1.67 | 12.60 | 5.50 | 22.88 |
| Uglegorsk 5-7 | 2400 | 2400 | 8,786 | 9 | 20.8 | 62% | 2.82 | 11.70 | 7.50 | 34.43 |
| Zaporozhe 1-4 | 1200 | 1092 | 8,973 | 9 | 13.5 | 69% | 1.85 | 12.60 | 5.50 | 24.18 |
| Zaporozhe 5-7 | 2400 | 2400 | 8,873 | 9 | 20.8 | 62% | 2.65 | 8.30 | 5.50 | 30.54 |
| CHP | 3000 | 2910 | 11,996 | 7 | 19.3 | 67% | 2.65 | 32.90 | 15.20 | 52.57 |
| Kharkov 1-2 | 206 | 206 | 11,996 | 4 | 26.5 | 66% | 2.65 | 20.70 | 6.20 | 41.58 |
| Kharkov 3 | 250 | 250 | 10,281 | 4 | 29.6 | 63% | 2.65 | 14.70 | 6.70 | 36.62 |
| Kiev/5 1-2 | 200 | 188 | 11,920 | 4 | 25.1 | 67% | 2.70 | 19.60 | 6.70 | 42.21 |
| Kiev/5 3-4 | 500 | 500 | 10,265 | 4 | 29.6 | 63% | 2.70 | 14.80 | 6.70 | 37.11 |
| Kiev/6 1-2 | 500 | 500 | 10,265 | 4 | 29.6 | 63% | 2.70 | 14.80 | 6.70 | 37.11 |
| Composite | 28,506 | 26,872 | 9,352 | | | 66% | 2.28 | | | 31.30 |
| Nuclear | | | | | | | | | | |
| Zaporozhe 1 | 1000 | 950 | 11,000 | 9 | 9.6 | 73% | 0.70 | 30 | 2.6 | 14.99 |
| Zaporozhe 2 | 1000 | 950 | 11,000 | 9 | 9.6 | 73% | 0.70 | 30 | 2.6 | 14.99 |
| Zaporozhe 3 | 1000 | 950 | 11,000 | 9 | 9.6 | 73% | 0.70 | 30 | 2.6 | 14.99 |
| Zaporozhe 4 | 1000 | 950 | 11,000 | 9 | 9.6 | 73% | 0.70 | 30 | 2.6 | 14.99 |
| Zaporozhe 5 | 1000 | 950 | 11,000 | 9 | 9.6 | 73% | 0.70 | 30 | 2.6 | 14.99 |
| Zaporozhe 6 | 1000 | 950 | 11,000 | 9 | 9.6 | 73% | 0.70 | 30 | 2.6 | 14.99 |
| So. Ukraine 1 | 1000 | 950 | 11,000 | 9 | 9.6 | 73% | 0.70 | 30 | 2.6 | 14.99 |
| So. Ukraine 2 | 1000 | 950 | 11,000 | 9 | 9.6 | 73% | 0.70 | 30 | 2.6 | 14.99 |
| So. Ukraine 3 | 1000 | 950 | 11,000 | 9 | 9.6 | 73% | 0.70 | 30 | 2.6 | 14.99 |
| Rovno 1 | 402 | 361 | 11,000 | 8 | 2 | 83% | 0.70 | 30 | 2.6 | 14.45 |
| Rovno 2 | 416 | 384 | 11,000 | 8 | 2 | 83% | 0.70 | 30 | 2.6 | 14.45 |
| Rovno 3 | 1000 | 950 | 11,000 | 9 | 9.6 | 73% | 0.70 | 30 | 2.6 | 14.99 |
| Khmelnitsky 1 | 1000 | 950 | 11,000 | 9 | 9.6 | 73% | 0.70 | 30 | 2.6 | 14.99 |
| Khmelnitsky 2 | 1000 | 950 | 11,000 | 9 | 9.6 | 73% | 0.70 | 30 | 2.6 | 14.99 |
| Rovno 4 | 1000 | 950 | 11,000 | 9 | 9.6 | 73% | 0.70 | 30 | 2.6 | 14.99 |

APPENDIX E

Plant Additions for Base Case Scenario

UKRAINE
K2/R4 Completion Due Diligence
Least-cost Planning Analysis

Plant Additions for Base Case Scenario

| Year | Plant Addition |
|------|---|
| 2000 | |
| 2001 | |
| 2002 | Khmelnitsky 2 Rovno 4 |
| 2003 | |
| 2004 | 4 X 300 MW High Level Rehabilitation |
| 2005 | 4 X 300 MW High Level Rehabilitation |
| 2006 | 2 X 300 MW High Level Rehabilitation 2 X 300 MW Low Level Rehabilitation |
| 2007 | 2 X 300 MW Low Level Rehabilitation |
| 2008 | 4 X 200 MW High Level Rehabilitation |
| 2009 | 4 X 200 MW High Level Rehabilitation |
| 2010 | 2 X 200 MW High Level Rehabilitation 4 X 200 MW Low Level Rehabilitation |
